US 20120223134A1

(19) **United States**

(12) **Patent Application Publication**

Smith et al.

(10) **Pub. No.: US 2012/0223134 A1**

(43) **Pub. Date: Sep. 6, 2012**

(54) **BANKING MACHINE CONTROLLED RESPONSIVE TO DATA READ FROM DATA BEARING RECORDS**

(75) Inventors: **Mark D. Smith**, North Canton, OH (US); **Natarajan Ramachandran**, Uniontown, OH (US); **James Block**, North Lawrence, OH (US); **Jeffery M. Enright**, Akron, OH (US)

(73) Assignee: **Diebold Self-Service Systems Division of Diebold, Incorporated**, North Canton, OH (US)

(21) Appl. No.: **13/443,230**

(22) Filed: **Apr. 10, 2012**

Related U.S. Application Data

(63) Continuation of application No. 13/199,600, filed on Sep. 2, 2011, which is a continuation of application No. 12/806,548, filed on Aug. 16, 2010, now Pat. No. 8,011,576, which is a continuation of application No. 11/821,227, filed on Jun. 22, 2007, now Pat. No. 7,789,295, which is a continuation of application No. 11/732,370, filed on Apr. 3, 2007, now Pat. No. 7,416,112.

(60) Provisional application No. 60/795,721, filed on Apr. 28, 2006, provisional application No. 60/789,644, filed on Apr. 5, 2006.

Publication Classification

(51) **Int. Cl.**


G06Q 40/02 (2012.01)

G07F 19/00 (2006.01)

(52) **U.S. Cl.** **235/379**; 705/43

(57) **ABSTRACT**

A banking system comprises automated banking machines which include a card reader, check imaging device, and cash dispenser. Each system machine can cash a code-correlated check in exchange for receiving both the check and the code assigned to the check, without requiring any user identifying input through the machine's user input devices as a condition for cashing the check. The system allows a potential recipient of a personal check to call in a given code to a system computer, which can verify whether the check is backed by funds reserved for the check amount and whether the check can be anonymously cashed. From the call the system computer can obtain the mobile phone's GPS location to determine the system machine nearest to the phone. When informing the phone user that a check is as good as cash, the system computer can also provide directions to that nearest system machine.





10
14
30
38
40
34
20
46
24
64
62
50
22
36
66
48
28
42
32
70
12
58
68
60
52
56
18
16

FIG. 1




FIG. 2



80
10
Bank
Service
78
22
34
44
76
Network
40
72
78
26
112
114
10
54

FIG. 3



72
82
80
Application
Operating System
Middleware
84
78
Diagnostics
86
88
Browser
90
Service Providers
92
94
98
96
32
44
26
54
Transaction Function Devices
100

FIG. 4




FIG. 5




FIG. 6




FIG. 7




FIG. 8




FIG. 9




FIG. 10



Run
136
Card In Reader
138
Sense Radiation Level
140
Compare to Stored Value
142
144
Yes
?
Difference In Excess of Threshold
No
Display Warning Screen
152
Send Status Message
154
Record Suspect Skim Transaction
156
Run Transaction Devices
158
Run Transaction Devices
146
Store New Value
148
Run
150

FIG. 11




FIG. 12




FIG. 13




FIG. 14




FIG. 15




Fig. 16



320
ATM #1 Data
ATM #2 Data
ATM #N Data
322
324
GPS Data from ATM #1
326
328
Match?
No
Yes
Track ATM Movement
338
Trip Alarm
336
Fire Dye Packs
334
Notify Authorities
332
ATM Secure
330

Fig. 17




Fig. 18



320
322
370
372
374
376
Location
Phone No.
Cell
ATM #1
ATM #2
ATM #3
ATM #N

Fig. 19



ATM
--GPS Location Data
--Service Request Data
Service Center
--ATM Location Data
--Service Type Needed
Navigation System

Fig. 20





Fig. 21

Fig. 22





Requester #1
Requester #2
Requester #3
384
386
388
Service Provider
380
382
ATM Location Data
Map Data
Other Data
390
392
394
396

Fig. 23

SP Action
Please Provide Pin
Please Provide Location
Please Provide Request
Generate Directions
Requester Action
Contact SP
Provide PIN
Provide Location
Provide Request
Receive Directions

Fig. 24




Fig. 25




Fig. 26




Fig. 27




Fig. 28



222
212
224
210
220
214
218
226
200
216
208
202
226
204
198
206
196

FIG. 29

BANKING MACHINE CONTROLLED RESPONSIVE TO DATA READ FROM DATA BEARING RECORDS

CROSS REFERENCE TO RELATED APPLICATIONS

[0001] This application is a continuation of U.S. Application 13/199,600 filed Sep. 2, 2011, which is a continuation of U.S. application Ser. No. 12/806,548 filed Aug. 16, 2010, now U.S. Pat. No. 8,011,576, which is a continuation of U.S. application Ser. No. 11/821,227 filed Jun. 22, 2007, now U.S. Pat. No. 7,789,295, which is a continuation of U.S. application Ser. No. 11/732,370 filed Apr. 3, 2007, now U.S. Pat. No. 7,416,112, which claims benefit pursuant to 35 U.S.C. §119 (e) of U.S. Provisional Applications 60/795,721 filed Apr. 28, 2006 and 60/789,644 filed Apr. 5, 2006. The entire disclosures of each and all of the foregoing applications are herein incorporated by reference as if fully rewritten herein.

[0002] The entire disclosures of each and all of the following applications are also herein incorporated by reference as if fully rewritten herein: U.S. Application 13/411,987 filed Mar. 5, 2012; U.S. application Ser. No. 12/586,468 filed Sep. 21, 2009; U.S. application Ser. No. 11/229,944 filed Sep. 19, 2005; U.S. Provisional Application 60/611,815 filed Sep. 20, 2004; U.S. Provisional Application 60/660,070 filed Mar. 9, 2005; U.S. application Ser. No. 10/832,960 filed Apr. 27, 2004; U.S. Provisional Application 60/560,674 filed Apr. 7, 2004; U.S. application Ser. No. 10/601,813 filed Jun. 23, 2003; and U.S. Provisional Application 60/429,478 filed Nov. 26, 2002.

TECHNICAL FIELD

[0003] This invention relates to apparatus controlled responsive to data read from data bearing records to cause financial transfers, which is classifiable in U.S. class 235, subclass 379.

BACKGROUND OF INVENTION

[0004] Automated banking machines may include a card reader that operates to read data from a bearer record, such as a user card. The machine may operate to cause the data read from the card to be compared with other computer-stored data related to authorized card bearers and/or financial accounts. The machine operates in response to the comparison determining that the bearer is an authorized system user to carry out at least one transaction which is operative to transfer value to or from at least one account. A record of the financial transaction is also commonly printed through operation of the machine and provided to the machine user.

[0005] A common type of automated banking machine used by consumers is an automated teller machine which enables customers to carry out banking transactions. Banking transactions carried out may include the dispensing of cash, the making of deposits, the transfer of funds between accounts, and account balance inquiries. The types of banking transactions a customer can carry out are determined by the capabilities of the particular banking machine, the system in which it is connected, and the programming of the institution operating the machine.

[0006] Other types of automated banking machines may be operated by merchants to carry out commercial transactions. These transactions may include, for example, the acceptance of deposit bags, the receipt of checks or other financial instruments, the dispensing of rolled coin, or other transactions required by merchants. Still, other types of automated banking machines may be used by service providers in a transaction environment such as at a bank to carry out financial transactions. Such transactions may involve, for example, the counting and storage of currency notes or other financial instrument sheets, the dispensing of notes or other sheets, the imaging of checks or other financial instruments, and other types of service provider transactions. Some types of automated banking machines may be operated as a self-service automated transaction machine that is capable of carrying out various transactions. For purposes of this disclosure, an automated banking machine or an automated teller machine (ATM) shall be deemed to include any machine that may be used to electronically carry out transactions involving transfers of value.

[0007] Automated banking machines may benefit from improvements.

OBJECTS OF EXEMPLARY EMBODIMENTS

[0008] It is an object of an exemplary embodiment to provide an automated banking machine.

[0009] It is a further object of an exemplary embodiment to provide an automated banking machine which provides for reliable illumination of transaction areas while facilitating servicing of the machine.

[0010] It is a further object of an exemplary embodiment to provide an automated banking machine that facilitates the detection of fraudulent activity which may be attempted at the machine.

[0011] It is a further object of an exemplary embodiment to provide an automated banking machine which improved capabilities.

[0012] It is a further object of an exemplary embodiment to provide an automated banking machine which reduces the risk of unauthorized access to devices and operations of the machine.

[0013] It is a further object of an exemplary embodiment to provide an automated banking machine with an improved security system.

[0014] It is a further object of an exemplary embodiment to provide an automated banking machine with a Global Positioning System (GPS).

[0015] Further objects of exemplary embodiments will be made apparent in the following Detailed Description of Exemplary Embodiments and the appended claims.

[0016] The foregoing objects are accomplished in some exemplary embodiments by an automated banking machine which includes a plurality of transaction function devices. In the exemplary embodiment the transaction function devices include input and output devices which are part of a user interface. In the exemplary embodiment the transaction function devices also include devices for carrying out types of banking transactions such as a currency dispenser device and a deposit accepting device. The exemplary automated banking machine also includes at least one computer which is generally referred to herein as a controller, and which is operative to cause the operation of the transaction function devices in the machine.

[0017] In an exemplary embodiment, the automated banking machine includes a housing with a secure chest portion and an upper housing area. The chest portion houses certain transaction function devices, such as the currency dispenser device. The chest portion includes a chest door which is

generally secured but which is capable of being opened when unlocked by authorized persons.

[0018] In the exemplary embodiment the upper housing area includes a first portion and a second portion. Access to the first and second portions are controlled by independently movable first and second fascia portions. In the exemplary embodiment one or more devices that must be manipulated in order to unlock the chest door are positioned within the first housing area. Access to the first portion of the upper housing is controlled by a fascia lock in operative connection with the first fascia portion.

[0019] In some exemplary embodiments during operation of the automated banking machine, the transaction areas are illuminated to facilitate operation of the machine by users. In an exemplary embodiment the controller of the automated banking machine is operative to illuminate the transaction areas at those times when the user would be expected to receive or place items in such transaction areas during the conduct of transactions. This facilitates guiding the user to the particular transaction area on the machine even when the machine is being operated during daylight hours.

[0020] In some exemplary embodiments the capability of illuminating selected areas of the machine during certain transaction steps may be utilized in conjunction with anti-fraud devices. In an exemplary embodiment anti-fraud devices are used to reduce the risk that an unauthorized card reading device is installed externally of the machine adjacent to the card reader slot of the machine fascia. Criminals are sometimes ingenious and in the past some have produced reading devices that can intercept magnetic stripe data on cards that are being input to an automated banking machine by a consumer. By intercepting this data, criminals may be able to conduct unauthorized transactions with the consumer's card number. Such external reading devices may be made to appear to be a part of the normal automated banking machine fascia.

[0021] In an exemplary embodiment the housing in surrounding relation of the card reader slot is illuminated responsive to operation of the controller. In some exemplary machines the housing is operative to illuminate an area generally entirely surrounding the slot so as to make it more readily apparent to a user that an unauthorized modification or attachment to the fascia may have been made.

[0022] In some exemplary embodiments during normal operation, the illumination of the area surrounding the fascia card slot is operative to help to guide the user to the slot during transactions when a user is required to input or take their card. The exemplary automated banking machine is provided with radiation sensing devices positioned adjacent to the illumination devices that are operative to illuminate the area surrounding the card reader slot. The exemplary controller is programmed to sense changes in the magnitude of radiation sensed by the one or more radiation sensing devices. The installation of an unauthorized card reading device in proximity to the card reading slot generally produces a change in the magnitude of the radiation sensed by the radiation sensing devices. The exemplary controller is programmed to recognize such changes and to take appropriate action in response thereto so as to reduce the possibility of fraud. Such action may include in some exemplary embodiments, the machine sending a status message through a network to a person to be notified of a possible fraud condition. Such actions may also include in some embodiments, warning the user of the machine to look for the installation of a possible fraud device. Of course these approaches are exemplary and in other embodiments other approaches may be used.

[0023] In some exemplary embodiments sensing devices may be provided in proximity to the keypad used by the customer to provide inputs, such as a personal identification number (PIN). Such sensors may be of the radiation sensing type or other type. Such sensors are adapted to sense the installation of unauthorized input intercepting devices above or adjacent to the keypad. The sensing of such an unauthorized device may cause an exemplary controller in the machine to give notice of the potential fraud device and/or to cease or modify the operation of the machine to reduce the risk of interception of customer inputs. In some exemplary embodiments radiation emitting devices used for sensing may provide outputs of visible light and may be used to guide a user at appropriate times during transactions to provide inputs to the keypad.

[0024] As will be appreciated, the foregoing objects and examples are exemplary and embodiments need not meet all or any of the foregoing objects, and need not include all or any of the exemplary features described above. Additional aspects and embodiments within the scope of the claims may be devised by those having skill in the art based on the teachings set forth herein.

BRIEF DESCRIPTION OF DRAWINGS

[0025] FIG. **1** is an isometric external view of an exemplary automated banking machine which incorporates some aspects and features of inventions in the present application.

[0026] FIG. **2** is a front plan view of the automated banking machine shown in FIG. **1**.

[0027] FIG. **3** is a transparent side view showing schematically some internal features of the automated banking machine.

[0028] FIG. **4** is a schematic view representative of the software architecture of an exemplary embodiment.

[0029] FIG. **5** is a front view showing the fascia portion moved to access a first portion of an upper housing of the machine.

[0030] FIG. **6** is a partially transparent side view showing air flow through an air cooling opening of the machine.

[0031] FIG. **7** is an isometric view of the automated banking machine shown in FIG. **1** with the components of the upper housing portion removed.

[0032] FIG. **8** is a schematic side view of the housing showing schematically the illumination system for the transaction areas and representing in phantom the movement of the upper fascia portion so as to provide access for servicing.

[0033] FIG. **9** is a schematic view of an illumination and anti-fraud sensing device which bounds a card reader slot of an exemplary embodiment.

[0034] FIG. **10** is a schematic side view of an unauthorized card reading device in operative connection with a housing of the anti-fraud sensor.

[0035] FIG. **11** is a schematic view of exemplary logic for purposes of detecting the presence of an unauthorized card reading device in proximity to the card reader during operation of the automated banking machine.

[0036] FIG. **12** is an exemplary side, cross sectional view of a machine keypad.

[0037] FIG. **13** is a schematic representation of a sensor for sensing whether an unauthorized key input sensing device has been placed adjacent to the keypad.

[0038] FIG. **14** is a view of a keypad similar to FIG. **12** but with an unauthorized key input sensing device attached.

[0039] FIG. **15** is a schematic representation similar to FIG. **13**, but representing the change in reflected radiation resulting from the attachment of the unauthorized key input sensing device.

[0040] FIG. **16** shows an automated banking machine security arrangement.

[0041] FIG. **17** shows an arrangement for comparing GPS location data to stored location data.

[0042] FIG. **18** shows an automated banking machine with GPS.

[0043] FIG. **19** shows a database portion.

[0044] FIG. **20** shows an automated banking machine, service center, and navigation system relationship.

[0045] FIG. **21** shows communication among an automated banking machine, service center, and a servicer's device.

[0046] FIG. **22** shows a fraud prevention service arrangement.

[0047] FIG. **23** shows a service provider, database, and requester arrangement.

[0048] FIG. **24** shows a flowchart of a service process.

[0049] FIG. **25** shows data and voice communication between an automated banking machine and a call center.

[0050] FIG. **26** shows a call center in operative connection with a data store having corresponding caller ID data and automated banking machine location data.

[0051] FIG. **27** shows text-based communication between an automated banking machine and a service provider operator's workstation.

[0052] FIG. **28** shows an automated banking machine and an operator's workstation including voice to text software.

[0053] FIG. **29** shows an exemplary system arrangement that allows for the anonymous cashing of checks at automated banking machines.

DETAILED DESCRIPTION OF EXEMPLARY EMBODIMENTS

[0054] Referring now to the drawings and particularly to FIG. **1**, there is shown therein an exemplary embodiment of an automated transaction machine (e.g., automated banking machine) generally indicated **10**. In an exemplary embodiment, the automated banking machine **10** can be a self-service machine, such as a drive-up automated teller machine. However, the features described and claimed herein are not necessarily limited to automated banking machines of this type. The exemplary automated banking machine includes a housing **12**. Housing **12** includes an upper housing area **14** and a secure chest area **16** in a lower portion of the housing. Access to the chest area **16** is controlled by a chest door **18** which when unlocked by authorized persons in the manner later explained, enables gaining access to the interior of the chest area.

[0055] The exemplary automated banking machine **10** further includes a first fascia portion **20** and a second fascia portion **22**. Each of the fascia portions is movably mounted relative to the housing as later explained, which in the exemplary embodiment facilitates servicing.

[0056] The automated banking machine includes a user interface generally indicated **24**. The exemplary user interface includes input devices such as a card reader **26** (shown in FIG. **3**) which is in connection with a card reader slot **28** which extends in the second fascia portion. Other input devices of the exemplary user interface **24** include function keys **30** and a keypad **32**. The exemplary automated banking machine **10** also includes a camera **34** which also may serve as an input device for biometric features and the like. The exemplary user interface **24** also includes output devices such as a display **36**. Display **36** is viewable by an operator of the machine when the machine is in the operative condition through an opening **38** in the second fascia portion **22**. Further output devices in the exemplary user interface include a speaker **40**. A headphone jack **42** also serves as an output device. The headphone jack may be connected to a headphone provided by a user who is visually impaired to provide the user with voice guidance in the operation of the machine. The exemplary machine further includes a receipt printer **44** (see FIG. **3**) which is operative to provide users of the machine with receipts for transactions conducted. Transaction receipts are provided to users through a receipt delivery slot **46** which extends through the second fascia portion. Exemplary receipt printers that may be used in some embodiments are shown in U.S. Pat. No. 5,729,379 and U.S. Pat. No. 5,850,075, the disclosures of which are incorporated by reference herein. It should be understood that these input and output devices of the user interface **24** are exemplary and in other embodiments, other or different input and output devices may be used.

[0057] In the exemplary embodiment the second fascia portion has included thereon a deposit envelope providing opening **48**. Deposit envelopes may be provided from the deposit envelope providing opening to users who may place deposits in the machine. The second fascia portion **20** also includes a fascia lock **50**. Fascia lock **50** is in operative connection with the second fascia portion and limits access to the portion of the interior of the upper housing behind the fascia to authorized persons. In the exemplary embodiment fascia lock **50** comprises a key type lock. However, in other embodiments other types of locking mechanisms may be used. Such other types of locking mechanisms may include for example, other types of mechanical and electronic locks that are opened in response to items, inputs, signals, conditions, actions or combinations or multiples thereof.

[0058] The exemplary automated banking machine **10** further includes a delivery area **52**. Delivery area **52** is in connection with a currency dispenser device **54** which is alternatively referred to herein as a cash dispenser, which is positioned in the chest portion and is shown schematically in FIG. **3**. The delivery area **52** is a transaction area on the machine in which currency sheets are delivered to a user. In the exemplary embodiment the delivery area **52** is positioned and extends within a recessed pocket **56** in the housing of the machine.

[0059] Automated banking machine **10** further includes a deposit acceptance area **58**. Deposit acceptance area is an area through which deposits, such as deposit envelopes to be deposited by users, are placed in the machine. The deposit acceptance area **58** is in operative connection with a deposit accepting device positioned in the chest area **16** of the machine. Exemplary types of deposit accepting devices are shown in U.S. Pat. No. 4,884,769 and U.S. Pat. No. 4,597,330, the disclosures of which are incorporated herein by reference.

[0060] In the exemplary embodiment the deposit acceptance area serves as a transaction area of the automated banking machine and is positioned and extends within a recessed pocket **60**. It should be understood that while the exemplary embodiment of machine **10** includes an envelope deposit

accepting device and a currency sheet dispenser device, other or different types of transaction function devices may be included in automated banking machines and devices encompassed by the present invention. These may include for example, check and/or money order accepting devices, ticket accepting devices, stamp accepting devices, card dispensing devices, money order dispensing devices and other types of devices which are operative to carry out transaction functions.

[0061] In the exemplary embodiment the automated banking machine **10** includes certain illuminating devices which are used to illuminate transaction areas, some of which are later discussed in detail. First fascia portion **20** includes an illumination panel **62** for illuminating the deposit envelope providing opening. Second fascia portion **22** includes an illumination panel **64** for illuminating the area of the receipt delivery slot **46** and the card reader slot **28**. Further, an illuminated housing **66** later discussed in detail, bounds the card reader slot **28**. Also, in the exemplary embodiment an illuminating window **68** is positioned in the recessed pocket **56** of the delivery area **52**. An illuminating window **70** is positioned in the recessed pocket **60** of the deposit acceptance area **58**. It should be understood that these structures and features are exemplary and in other embodiments other structures and features may be used.

[0062] As schematically represented in FIG. **3**, the automated banking machine **10** includes one or more internal computers. Such internal computers include one or more processors. Such processors may be in operative connection with one or more data stores. In some embodiments, processors may be located on certain devices within the automated banking machine so as to individually control the operation thereof. Examples such as multi-tiered processor systems are shown in U.S. Pat. No. 6,264,101 and U.S. Pat. No. 6,131,809, the disclosures of which are incorporated herein by reference.

[0063] For purposes of simplicity, the exemplary embodiment will be described as having a single controller which controls the operation of devices within the machine. However it should be understood that such reference shall be construed to encompass multicontroller and multiprocessor systems as may be appropriate in controlling the operation of a particular machine. In FIG. **3** the controller is schematically represented **72**. Also as schematically represented, the controller is in operative connection with one or more data stores **78**. Such data stores in exemplary embodiments are operative to store program instructions, values and other information used in the operation of the machine. Although the controller is schematically shown in the upper housing portion of automated banking machine **10**, it should be understood that in alternative embodiments controllers may be located within various portions of the automated banking machine.

[0064] In order to conduct transactions, the exemplary automated banking machine **10** communicates with remote computers. The remote computers are operative to exchange messages with the machine and authorize and record the occurrence of various transactions. This is represented in FIG. **3** by the communication of the machine through a network with a bank **78**, which has at least one computer which is operative to exchange messages with the automated banking machine through a network. For example, the bank **78** may receive one or more messages from the machine requesting authorization to allow a customer to withdraw $200 from the customer's account. The remote computer at the bank **78** will operate to determine that such a withdrawal is authorized and will return one or more messages to the machine through the network authorizing the transaction. After the machine conducts the transaction, the machine will generally send one or more messages back through the network to the bank indicating that the transaction was successfully carried out. Of course these messages are merely exemplary.

[0065] It should be understood that in some embodiments the automated banking machine may communicate with other entities and through various networks. For example as schematically represented in FIG. **3**, the machine will communicate with computers operated by service providers **80**. Such service providers may be entities to be notified of status conditions or malfunctions of the machine as well as entities who are to be notified of corrective actions. An example of such a system for accomplishing this is shown in U.S. Pat. No. 5,984,178, the disclosure of which is incorporated herein by reference. Other third parties who may receive notifications from exemplary automated banking machines include entities responsible for delivering currency to the machine to assure that the currency supplies are not depleted. Other entities may be responsible for removing deposit items from the machine. Alternative entities that may be notified of actions at the machine may include entities which hold marketing data concerning consumers and who provide messages which correspond to marketing messages to be presented to consumers. Various types of messages may be provided to remote systems and entities by the machine depending on the capabilities of the machines in various embodiments and the types of transactions being conducted.

[0066] FIG. **4** shows schematically an exemplary software architecture which may be operative in the controller **72** of machine **10**. The exemplary software architecture includes an operating system such as for example Microsoft® Windows, IBM OS/2® or Linux. The exemplary software architecture also includes an automated banking machine application **82**. The exemplary application includes the instructions for the operation of the automated banking machine and may include, for example, an Agilis™ 91x application that is commercially available from Diebold, Incorporated which is a cross vendor software application for operating automated banking machines. Further examples of software applications which may be used in some embodiments are shown in U.S. Pat. Nos. 6,289,320 and 6,505,177, the disclosures of which are incorporated herein by reference.

[0067] In the exemplary embodiment middleware software schematically indicated **84** is operative in the controller. In the exemplary embodiment the middleware software operates to compensate for differences between various types of automated banking machines and transaction function devices used therein. The use of a middleware layer enables the more ready use of an identical software application on various types of automated banking machine hardware. In the exemplary embodiment the middleware layer may be Involve® software which is commercially available from Nexus Software, a wholly owned subsidiary of the assignee of the present invention.

[0068] The exemplary software architecture further includes a diagnostics layer **86**. The diagnostics layer **86** is operative as later explained to enable accessing and performing various diagnostic functions of the devices within the automated banking machine. In the exemplary embodiment the diagnostics operate in conjunction with a browser schematically indicated **88**.

[0069] The exemplary software architecture further includes a service provider layer schematically indicated **90**. The service provider layer may include software such as WOSA XFS service providers for J/XFS service providers which present a standardized interface to the software layers above and which facilitate the development of software which can be used in conjunction with different types of automated banking machine hardware. Of course this software architecture is exemplary and in other embodiments other architectures may be used.

[0070] As schematically represented in FIG. **4**, a controller **72** is in operative connection with at least one communications bus **92**. The communications bus may in some exemplary embodiments be a universal serial bus (USB) or other standard or nonstandard type of bus architecture. The communications bus **92** is schematically shown in operative connection with transaction function devices **94**. The transaction function devices include devices in the automated banking machine which are used to carry out transactions. These may include for example the currency dispenser device **54**, card reader **26**, receipt printer **44**, keypad **32**, as well as numerous other devices which are operative in the machine and controlled by the controller to carry out transactions. In the exemplary embodiment one of the transaction function devices in operative connection with the controller is a diagnostic article reading device **96** which may be operative to read a diagnostic article schematically indicated **98** which may provide software instructions useful in servicing the machine. Alternatively and/or in addition, provision may be made for connecting the bus **92** or other devices in the machine computer device **100** which may be useful in performing testing or diagnostic activities related to the automated banking machine.

[0071] In the exemplary embodiment of automated banking machine **10**, the first fascia portion **20** and the second fascia portion **22** are independently movably mounted on the machine housing **12**. This is accomplished through the use of hinges attached to fascia portion **20**. The opening of the fascia lock **50** on the first fascia portion **20** enables the first fascia portion to be moved to an open position as shown in FIG. **5**. In the open position of the first fascia portion an authorized user is enabled to gain access to a first portion **102** in the upper housing area **14**. In the exemplary embodiment there is located within the first portion **102** a chest lock input device **104**. In this embodiment the chest lock input device comprises a manual combination lock dial, electronic lock dial or other suitable input device through which a combination or other unlocking inputs or articles may be provided. In this embodiment, input of a proper combination enables the chest door **18** to be moved to an open position by rotating the door about hinges **106**. In the exemplary embodiment the chest door is opened once the proper combination has been input by manipulating a locking lever **108** which is in operative connection with a boltwork. The boltwork which is not specifically shown, is operative to hold the chest door in a locked position until the proper combination is input. Upon input of the correct combination the locking lever enables movement of the boltwork so that the chest door can be opened. The boltwork also enables the chest door to be held locked after the activities in the chest portion have been conducted and the chest door is returned to the closed position. Of course in other embodiments other types of mechanical or electrical locking mechanisms may be used. In the exemplary embodiment the chest lock input device **104** is in supporting connection with a generally horizontally extending dividing wall **110** which separates the chest portion from the upper housing portion. Of course this housing structure is exemplary and in other embodiments other approaches may be used.

[0072] An authorized servicer who needs to gain access to an item, component, or device that is located in the automated banking machine's chest area may do so by opening the fascia lock and moving the first fascia portion **20** so that the area **102** becomes accessible. Thereafter the authorized servicer may access and manipulate the chest lock input device to receive one or more inputs, which if appropriate enables unlocking of the chest door **18**. The chest door may thereafter be moved relative to the housing and about its hinges **106** to enable the servicer to gain access to items, devices or components within the chest. These activities may include for example adding or removing currency, removing deposited items such as envelopes or checks, or repairing mechanisms or electrical devices that operate to enable the machine to accept deposited items or to dispense currency. When servicing activity within the chest is completed, the chest door may be closed and the locking lever **108** moved so as to secure the boltwork holding the chest door in a closed position. Of course this structure and service method is exemplary and in other embodiments other approaches may be used.

[0073] In the exemplary embodiment the second fascia portion **22** is also movable relative to the housing of the machine. In the exemplary embodiment the second fascia portion **22** is movable in supporting connection with a rollout tray **112** schematically shown in FIG. **3**. The rollout tray is operative to support components of the user interface thereon as well as the second fascia portion. The rollout tray enables the second fascia portion to move outward relative to the machine housing thereby exposing components and transaction function devices supported on the tray and providing access to a second portion **114** within the upper housing and positioned behind the second fascia portion. Thus, as can be appreciated, when the second fascia portion is moved outward, the components on the tray are disposed outside the housing of the machine so as to facilitate servicing, adjustment and/or replacement of such components. Further components which remain positioned within the housing of the machine as the rollout tray is extended, become accessible in the second portion as the second fascia portion **22** is disposed outward and away from the housing.

[0074] In the exemplary embodiment the rollout tray **112** is in operative connection with a releasible locking device. The locking device is generally operative to hold the tray in a retracted position such that the second fascia portion remains in an operative position adjacent to the upper housing area as shown in FIGS. **1**, **2**, and **3**. This releasible locking mechanism may comprise one or more forms of locking type devices. In the exemplary embodiment the releasible locking mechanism may be released by manipulation of an actuator **116** which is accessible to an authorized user in the first portion **102** of the upper housing **14**. As a result an authorized servicer of the machine is enabled to move the second fascia portion outward for servicing by first accessing portion **102** in the manner previously discussed. Thereafter by manipulating the actuator **116** the second fascia portion is enabled to move outward as shown in phantom in FIG. **8** so as to facilitate servicing components on the rollout tray. Such components may include for example a printer or card reader. After such servicing the second fascia portion may be moved toward the housing so as to close the second portion **114**. Such move-

ment in the exemplary embodiment causes the rollout tray to be latched and held in the retracted position without further manipulation of the actuator. However, in other embodiments other types of locking mechanisms may be used to secure the rollout tray in the retracted position. It should be understood that this approach is exemplary and in other embodiments other approaches may be used.

[0075] As best shown in FIG. **7** in which the components supported in the upper housing are not shown, the delivery area **52** and the deposit acceptance area **58** are in supporting connection with the chest door **18**. As such when the chest door **18** is opened, the delivery area **52** and the deposit acceptance area **58** will move relative to the housing of the machine. The exemplary embodiment shown facilitates servicing of the machine by providing for the illumination for the transaction areas by illumination sources positioned in supporting connection with the rollout tray **112**. As best shown in FIG. **6**, these illumination sources **118** are movable with the rollout tray and illuminate in generally a downward direction. In the operative position of the second fascia portion **22** and the chest door **18**, the illumination sources are generally aligned with apertures **120** and **122** which extend through the top of a cover **124** which generally surrounds the recessed pockets **60** and **56**. As shown in FIG. **10** aperture **120** is generally vertically aligned with window **68** and aperture **122** is generally aligned with window **70**. In an exemplary embodiment, apertures **120** and **122** each have a translucent or transparent lens positioned therein to minimize the risk of allowing dirt or other contaminants into the interior of the cover **124**.

[0076] As can be appreciated from FIGS. **6** and **8**, when the chest door **18** is closed and the second fascia portion **22** is moved to the operative position, the illumination sources **118** are positioned in generally aligned relation with apertures **120** and **122**. As a result the illumination of the illumination devices is operative to cause light to be transmitted through the respective aperture and to illuminate the transaction area within the corresponding recessed pocket.

[0077] In operation of an exemplary embodiment, the controller executes programmed instructions so as to initiate illumination of each transaction area at appropriate times during the conduct of transactions. For example in the exemplary embodiment if the user is conducting a cash withdrawal transaction, the controller may initiate illumination of the delivery area **52** when the cash is delivered therein and is available to be taken by a user. Such illumination draws the user's attention to the need to remove the cash and will point out to the user that the cash is ready to be taken. In the exemplary embodiment the controller is programmed so that when the user takes the cash the machine will move to the next transaction step. After the cash is sensed as taken, the controller may operate to cease illumination of the delivery area **56**. Of course these approaches are exemplary.

[0078] Likewise in an exemplary embodiment if a user of the machine indicates that they wish to conduct a deposit transaction, the controller may cause the machine to operate to initiate illumination of the deposit acceptance area **58**. The user's attention is drawn to the place where they must insert the deposit envelope in order to have it be accepted in the machine. In the exemplary embodiment the controller may operate to also illuminate the illumination panel **62** to illuminate the deposit envelope providing opening **48** so that the user is also made aware of the location from which a deposit envelope may be provided. In an exemplary embodiment the controller may operate to cease illumination through the window **70** and/or the illumination panel **62** after the deposit envelope is indicated as being sensed within the machine.

[0079] In alternative embodiments other approaches may be taken. This may include for example drawing the customer's attention to the particular transaction area by changing the nature of the illumination in the recessed pocket to which the customer's attention is to be drawn. This may be done for example by changing the intensity of the light, flashing the light, changing the color of the light or doing other actions which may draw a user's attention to the appropriate transaction area. Alternatively or in addition, a sound emitter, vibration, projecting pins or other indicator may be provided for visually impaired users so as to indicate to them the appropriate transaction area to which the customer's attention is to be drawn. Of course these approaches are exemplary and in other embodiments other approaches may be used.

[0080] As previously discussed, the exemplary embodiment of the automated banking machine **10** is also operative to draw a user's attention at appropriate times to the card reader slot **28**. machine **10** also includes features to minimize the risk of unauthorized interception of card data by persons who may attempt to install a fraud device such as an unauthorized card reading device on the machine. As shown in FIG. **9**, the exemplary card slot **28** extends through a card slot housing **66** which extends in generally surrounding relation of the card slot. It should be understood that although the housing **66** generally bounds the entire card slot, in other embodiments the principles described herein may be applied by bounding only one or more sides of a card slot as may be appropriate for detecting unauthorized card reading devices. Further, it should be understood that while the exemplary embodiment is described in connection with a card reader that accepts a card into the machine, the principles being described may be applied to types of card readers that do not accept a card into the machine, such as readers where a user draws the card through a slot, inserts and removes a card manually from a slot and other card reading structures.

[0081] In the exemplary embodiment the housing **66** includes a plurality of radiation emitting devices **126**. The radiation emitting devices emit visible radiation which can be perceived by a user of the machine. However, in other embodiments the radiation emitting devices may include devices which emit nonvisible radiation such as infrared radiation, but which nonetheless can be used for sensing the presence of unauthorized card reading devices adjacent to the card slot. In the exemplary embodiment the controller operates to illuminate the radiation emitting devices **126** at appropriate times during the transaction sequence. This may include for example times during transactions when a user is prompted to input the card into the machine or alternatively when a user is prompted to take the card from the card slot **28**. In various embodiments the controller may be programmed to provide solid illumination of the radiation emitting devices or may vary the intensity of the devices as appropriate to draw the user's attention to the card slot.

[0082] In the exemplary embodiment the card slot housing **66** includes therein one or more radiation sensing devices **128**. The radiation sensing devices are positioned to detect changes in at least one property of the radiation reflected from the emitting devices **126**. The sensing devices **128** are in operative connection with the controller. The controller is operative responsive to its programming to compare one or more values corresponding to the magnitude and/or other properties of radiation sensed by one or more of the sensors,

to one or more stored values and to make a determination whether the comparison is such that there is a probable unauthorized card reading device installed on the fascia of the machine. In some embodiments the controller may be operative to execute fuzzy logic programming for purposes of determining whether the nature of the change in reflected radiation and/or other detected parameters are such that there has been an unauthorized device installed and whether appropriate personnel should be notified.

[0083] FIG. **10** shows a side view of the housing **66**. An example of a fraud device which comprises unauthorized card reading device **130** is shown attached externally to the housing **66**. The unauthorized card reading device includes a slot **132** generally aligned with slot **128**. The device **130** also includes a sensor shown schematically as **134** which is operative to sense the encoded magnetic flux reversals which represent data on the magnetic stripe of a credit or debit card. As can be appreciated, an arrangement of the type shown in FIG. **10** enables the sensor **134** if properly aligned adjacent to the magnetic stripe of a card, to read the card data as the card passes in and out of slot **128**. Such an unauthorized reading device may be connected via radio frequency (RF) or through inconspicuous wiring to other devices which enable interception of the card data. In some situations criminals may also endeavor to observe the input of the user's PIN corresponding to the card data so as to gain access to the account of the user.

[0084] As can be appreciated from FIG. **10** the installation of the unauthorized card reading device **130** changes the amount of radiation from emitting devices **126** and that is reflected or otherwise transmitted to the sensors **128**. Depending on the nature of the device and its structure, the amount or other properties of radiation may increase or decrease. However, a detectable change will often occur in the magnitude or other properties of sensed radiation between a present transaction and a prior transaction which was conducted prior to an unauthorized card reading device being installed. Of course the sensing of the magnitude of radiation is but one example of a property of radiation that may be sensed as having changed so as to indicate the presence of an unauthorized reading device.

[0085] FIG. **11** demonstrates an exemplary simplified logic flow executed by a controller for detecting the installation of an unauthorized card reading device. It should be understood that this transaction logic is part of the overall operation of the machine to carry out transactions. In this exemplary logic flow the machine operates to carry out card reading transactions in a normal manner and to additionally execute the represented steps as a part of such logic each time a card is read. From an initial step **136** the controller in the machine is operative to sense that a card is in the reader within the machine in a step **138**. Generally in these circumstances the controller will be operating the radiation emitting devices **126** as the user has inserted their card and the card has been drawn into the machine. In this exemplary embodiment the controller continues to operate the radiation emitting devices and senses the radiation level or levels sensed by one or more sensors **128**. This is done in a step **140**.

[0086] The controller is next operative to compare the signals corresponding to the sensed radiation levels to one or more values in a step **142**. This comparison may be done a number of ways and may in some embodiments execute fuzzy logic so as to avoid giving false indications due to acceptable conditions such as a user having the user's finger adjacent to the card slot **28** during a portion of the transaction. In the case of a user's finger for example, the computer may determine whether an unauthorized reading device is installed based on the nature, magnitude and changes during a transaction in sensed radiation, along with appropriate programmed weighing factors. Of course various approaches may be used within the scope of the concept discussed herein. However, based on the one or more comparisons in step **142** the controller is operative to make a decision at step **144** as to whether the sensed value(s) compared to stored value(s) compared in step **142** have a difference that is in excess of one or more thresholds which suggest that an unauthorized card reading device has been installed.

[0087] If the comparison does not indicate a result that exceeds the threshold(s), the automated banking machine transaction devices are run as normal as represented in a step **146**. For example, a customer may be prompted to input a PIN, and if the card data and PIN are valid, the customer may be authorized to conduct a cash dispensing transaction through operation of the machine. Further in the exemplary embodiment, the controller may operate to adjust the stored values to some degree based on the more recent readings. This may be appropriate in order to compensate for the effects of dirt on the fascia or loss of intensity of the emitting devices or other factors. This is represented in a step **148**. In step **148** the controller operates the automated banking machine to conduct transaction steps in the usual manner as represented in a step **150**.

[0088] If in step **144** the difference between the sensed and stored values exceeds the threshold(s), then this is indicative that an unauthorized card reading device may have been installed since the last transaction. In the exemplary embodiment when this occurs, the controller is operative to present a warning screen to the user as represented in a step **152**. This warning screen may be operative to advise the user that an unauthorized object has been sensed adjacent to the card reader slot. This may warn a user for example that a problem is occurring. Alternatively if a user has inadvertently placed innocently some object adjacent to the card reader slot, then the user may withdraw it. In addition or in the alternative, further logic steps may be executed such as prompting a user to indicate whether or not they can see the radiation emitting devices being illuminated adjacent to the card slot and prompting the user to provide an input to indicate if such items are visible. Additionally or in the alternative, the illuminating devices within the housing **66** may be operative to cause the emitting devices to output words or other symbols which a user can indicate that they can see or cannot see based on inputs provided as prompts from output devices of the machine. This may enable the machine to determine whether an unauthorized reading device has been installed or whether the sensed condition is due to other factors. It may also cause a user to note the existence of the reading device and remove it. Of course various approaches could be taken depending on the programming of the machine.

[0089] If an unauthorized reading device has been detected, the controller in the exemplary embodiment will also execute a step **154** in which a status message is sent to an appropriate service provider or other entity to indicate the suspected problem. This may be done for example through use of a system like that shown in U.S. Pat. No. 5,984,178 the disclosure of which is incorporated herein by reference. Alternatively messages may be sent to system addresses in a manner like that shown in U.S. Pat. No. 6,289,320 the disclosure of which is also incorporated herein by reference. In a step **156**

the controller will also operate to record data identifying for the particular transaction in which there has been suspected interception of the card holder's card data. In addition or in the alternative, a message may be sent to the bank or other institution alerting them to watch for activity in the user's card account for purposes of detecting whether unauthorized use is occurring. Alternatively or in addition, some embodiments may include card readers that change, add or write data to a user's card in cases of suspected interception. Such changed data may be tracked or otherwise used to assure that only a card with the modified data is useable thereafter. Alternatively or in addition, in some embodiments the modified card may be moved in translated relation, moved irregularly or otherwise handled to reduce the risk that modified data is intercepted as the card is output from the machine. Of course these approaches are exemplary of many that may be employed.

[0090] In the exemplary embodiment, the automated banking machine is operated to conduct a transaction even in cases where it is suspected that an unauthorized card reading device has been installed. This is represented in a step **158**. However, in other embodiments other approaches may be taken such as refusing to conduct the transaction. Other steps may also be taken such as capturing the user's card and advising the user that a new one will be issued. This approach may be used to minimize the risk that unauthorized transactions will be conducted with the card data as the card can be promptly invalidated. Of course other approaches may be taken depending on the programming of the machine and the desires of the system operator. In addition while the fraud device shown is an unauthorized card reading device, the principles described may also be used to detect other types of fraud devices such as for example false fascias, user interface covers and other devices.

[0091] In some embodiments additional or alternative features and methods may be employed to help detect the presence of unauthorized card reading devices or other attempted fraud devices in connection with the automated banking machine. For example in some embodiments an oscillation sensor may be attached to the machine to detect changes in frequency or vibration that result from the installation of unauthorized devices on the machine. FIG. **10** shows schematically an oscillator **127** attached to the interior surface of the machine fascia. Oscillator **127** may be operative responsive to the controller and suitable vibration circuitry to impart vibratory motion to the fascia in the vicinity of the card reader slot. A sensor **129** is in operative connection with the fascia and is operative to sense at least one parameter of the motion imparted to the fascia by the oscillator **127**. Although oscillator **127** and sensor **129** are shown as separate components, it should be understood that in some embodiments the functions of the components may be performed by a single device.

[0092] The sensor **129** is in operative connection with the controller of the automated banking machine through appropriate circuitry. The controller selectively activates the oscillator and the sensor **129** is operative to sense the resulting movement of the fascia caused by the oscillation. The installation of an unauthorized card reading device or other fraud device on the machine will generally result in a change in at least one property being sensed by the sensor **129**. This may include changes in amplitude, frequency or both. Alternatively or in addition, some embodiments may provide for the oscillator to impart vibration characteristics of various types or vibratory motion through a range of frequencies and/or amplitudes. Sensed values for various oscillatory driving outputs may then be compared through operation of the controller to one or more previously stored values. Variances from prior values may be detected or analyzed through operation of the controller and notifications given in situations where a change has occurred which suggests the installation of an unauthorized device.

[0093] In some embodiments the controller may cause the oscillator and sensor to operate periodically to sense for installation of a possible unauthorized device. Alternatively, the controller may cause such a check to be made during each transaction. Alternatively in some embodiments oscillation testing may be conducted when a possible unauthorized device is detected by sensing radiation properties. The controller may operate to take various actions in response to sensing a possible unauthorized reading device through vibration, radiation or both. For example detecting a possible fraud device by both radiation and oscillation may warrant taking different actions than only detecting a possible fraud device through only one test or condition.

[0094] In some embodiments the controller may be programmed to adjust the thresholds or other limits used for resolving the presence of a possible fraud device for responses to changes that occur over time at the machine. This may include for example adjusting the thresholds for indicating possible fraud conditions based on the aging of the oscillator or the sensor. Such adjustments may also be based on parameters sensed by other sensors which effect vibration properties. These may include for example, the fascia temperature, air temperature, relative humidity and other properties. Of course readings from these and other sensors may be used to adjust thresholds of the oscillation sensor, radiation sensor or other fraud device sensors. Various approaches may be taken depending on the particular system.

[0095] In some embodiments the oscillator may additionally or alternatively be used to prevent the unauthorized reading of card reader signals. This may be done for example when the banking machine has a device which takes a user card into the machine for purposes of reading data on the card. In such embodiments the controller may operate to vibrate the area of the fascia adjacent to the card reader slot when a user's card is moving into and/or out of the slot. In such cases the vibration may be operative to cause the generation of noise or inaccurate reading by an unauthorized card reading sensor so as to make it more difficult to intercept the card stripe data using an unauthorized reading device. In some embodiments such vibration may also serve to disclose or make more apparent, the presence of unauthorized card reading devices. Of course these approaches are exemplary and in other embodiments other approaches may be used.

[0096] In some exemplary embodiments provision may be made for detecting the presence of unauthorized input sensing devices for sensing a user's inputs through a keypad of the automated banking machine. Such unauthorized input sensing devices may be used by criminals to sense the PIN input by the user. Detecting unauthorized devices may be accomplished by providing appropriate sensing devices in or adjacent to the keypad. Such sensing devices may be operative to detect that a structure has been placed over or adjacent to the keypad. Such sensors may be in operative connection with the controller in the machine or other devices which are operative to determine the probable installation of such an unauthorized input sensing device. In response to determining the probable installation of such a device, the controller may be operative

in accordance with its programming to provide notification to appropriate entities, modify the operation of the machine such as to disable operation or prevent certain operations, or to take other appropriate actions.

[0097] FIG. **12** shows the cross-sectional view of exemplary keypad **32**. Keypad **32** is shown schematically, and it should be understood that not all of the components of the keypad are represented. Keypad **32** includes a plurality of keys **250**. Keys **250** are moveable responsive to pressure applied by a user's finger to provide an input corresponding to alphabetical or numerical characters. Extending between some of the keys **250** are areas or spaces **252**. Extending in spaces **252** are sensors **254**. In the exemplary embodiment the sensors **254** are radiation type sensors, but as previously discussed, in other embodiments other approaches may be used. Overlying the sensors **254** is an outer layer **256**. In the exemplary embodiment, layer **256** is translucent or otherwise comprised of material so as to partially enable the transmission of radiation from the sensors therethrough.

[0098] As represented in FIG. **13**, the exemplary sensors **254** include a radiation emitter **258** and a radiation receiver **260**. During operation the radiation emitter is operative to output radiation that is at least partially reflected from the inner surface of layer **256**. The reflected radiation is received by the receiver **260**. Corresponding electrical signals are produced by the receiver, and such signals are transmitted through appropriate circuitry so as to enable the controller to detect the changes in signals that correspond to probable presence of an unauthorized reading device.

[0099] FIG. **14** is a schematic view of an unauthorized input intercepting device **262** that has been positioned in overlying relation of a keypad **32**. The input intercepting device **262** includes false keys **264** which are moveable and which are operatively connected to the corresponding keys **250** of the keypad. In the exemplary embodiment, input intercepting device **262** includes sensors which are operative to detect which of the false keys **264** have been depressed by a user. Because the depression of the false keys is operative to actuate the actual keys **250**, the automated banking machine is able to operate with the device **262** in place. Input intercepting device **262** in exemplary embodiments may include a wireless transmitter or other suitable device for transmitting the input signals to a criminal who may intercept such inputs. As represented in FIG. **19**, the input intercepting device **262** includes portions **267** which extend in the areas **252** in overlying relation of layer **256**. As represented in FIG. **15**, the portion of the input intercepting device extending in overlying relation of the layer **256** is operative to cause a change in the amount of radiation from the emitter **258** that is reflected and sensed by the receiver **260** of the sensor. This is because the overlying portion will have different radiation reflecting or absorbing characteristics which will change the radiation reflective properties of the layer **256** compared to when no such input intercepting device is present. Thus, the installation of the unauthorized input intercepting device can be detected.

[0100] In some exemplary embodiments the controller may be operative to sense the level of reflected radiation at the sensors periodically. This may be done, for example, between transactions when a user is not operating the terminal. This may avoid giving a false indication that an unauthorized input intercepting device has been installed when a user is resting a hand or some other item adjacent to the keypad during a transaction. Of course in other embodiments sensor readings can be taken and compared during transactions to prior values stored in a data store to determine if a change lasting longer than normal has occurred which suggests that an unauthorized input intercepting device has been installed rather than a user has temporarily placed their hand or some other item adjacent to the keypad. For example, in some exemplary embodiments the controller may not resolve that there is a probable unauthorized input intercepting device on the machine until a significant change from a prior condition is detected in the radiation properties adjacent to the keypad on several occasions both during a transaction and thereafter. Alternatively or in addition, a controller may be operative to determine that an improper device has been installed as a result of changes that occur during a time when no transactions have occurred. Alternatively in other embodiments, the controller may operate to sense and analyze signals from the sensors responsive to detecting inputs from other sensors, such as for example an ultrasonic sensor which senses that a person has moved adjacent to the machine but has not operated the machine to conduct a transaction. Of course these approaches are merely exemplary of many approaches that may be used.

[0101] It should be understood that although in the exemplary embodiment radiation type sensors are used for purposes of detection, in other embodiments other types of sensors may be used. These include, for example, inductance sensors, sonic sensors, RF sensors, or other types of sensing approaches that can be used to detect the presence of material in locations that suggest an unauthorized input intercepting device being positioned adjacent to the keypad. Further, in some embodiments the controller or other circuitry associated with the sensors may be operative to make adjustments for normal changes that may occur at the machine. These may include, for example, changes with time due to aging of emitters, the build up of dirt in the area adjacent to the keypad, weather conditions, moisture conditions, scratching of the surface of the sensing layer, or other conditions which may normally occur. Appropriate programs may be executed by the controller or other circuitry so as to recalibrate and/or compensate for such conditions as may occur over time while still enabling the detection of a rapid change which is sufficiently significant and of such duration so as to indicate the probable installation of an unauthorized input intercepting device. Of course these approaches are exemplary of many approaches that may be used.

[0102] In other embodiments other or additional approaches to detecting fraudulent reading or other improper activities may be used. For example, in some embodiments the fascia of the banking machine may be subject to observation within a field of view of one or more imaging devices such as camera **131** schematically represented in FIG. **10**. Camera **15** may be in operative connection with an image capture system of the type shown in U.S. Pat. No. 6,583,813, the disclosure of which is incorporated herein by reference.

[0103] In some embodiments the controller and/or an image capture system may be operative to execute sequences of activities responsive to triggering events that may be associated with attempts to install or operate fraud devices. For example, the presence of a person in front of the banking machine may be sensed through image analysis, weight sensors, sonic detectors or other detectors. The person remaining in proximity to the machine for a selected period or remaining too long after a transaction may constitute a triggering event which is operative to cause the system to take actions in a

programmed sequence. Such actions may include capturing images from one or more additional cameras and/or moving image data from one or more cameras from temporary to more permanent storage. The sequence may also include capturing image data from the fascia to try to detect tampering or improper devices. Radiation or vibration tests may also be conducted as part of a sequence. Notifications and/or images may also be sent to certain entities or system addresses. Of course these actions are exemplary.

[0104] In some exemplary embodiments, the controller of the automated banking machine or other connected computers may be operatively programmed to analyze conditions that are sensed and to determine based on the sensed conditions that a fraud device is installed. Such a programmed computer may be operative to apply certain rules, such as to correlate the repeated sensing of abnormal conditions with a possible fraud or tampering condition, and to conduct tests for the presence of fraud devices. Such events may constitute soft triggers for sequences or other actions to detect and reduce the risk of fraud devices. Of course these approaches are merely exemplary and in other embodiments other approaches may be used.

[0105] In some embodiments, the automated banking machine may include sensors adapted to intercept signals from unauthorized card readers or customer input intercepting devices. For example, some fraud devices may operate to transmit RF signals to a nearby receiver operated by a criminal. The presence of such RF signals in proximity to the machine may be indicative of the installation of such a device. Such signals may be detected by appropriate circuitry and analyzed through operation of the machine controller or other processor, and if it is determined that it is probable that such a device is installed, programmed actions may be taken.

[0106] For example, in some embodiments suitable RF shielding material may be applied to or in the fascia to reduce the level of RF interference from devices within the automated banking machine at the exterior of the fascia. Antennas or other appropriate radiation sensing devices may be positioned adjacent to or installed on the fascia. A change in RF radiation in the vicinity of the fascia exterior may result upon the installation of an unauthorized device. The RF signals can be detected by receiver circuitry, and signals or data corresponding thereto being input to a processor. In some embodiments the circuitry may also determine the frequency of the radiation sensed to be used in resolving if it is within the range emitted by legitimate devices such as cell phones of users operating the machine. In other embodiments the circuitry may analyze the signals to determine if they are varying, and the circuitry and/or the processor may evaluate whether the changes in signal correspond to the input of a PIN or a card to the machine.

[0107] In response to the sensed signal data, the processor may operate in accordance with its programming to evaluate the nature and character of the intercepted signals. For example, if the signals do not correspond to a legitimate source, such as a cell phone, the processor may operate to take actions such as to wholly or partially cease operation of the automated banking machine, capture images with a camera, and/or notify an appropriate remote entity through operation of the machine. Alternatively, the processor may compare the sensed RF signals to transaction activity at the machine. If the sensed signals are determined to be varying in ways that correspond in a pattern or relationship to card or PIN inputs, for example, the processor may operate in accordance with its programming to cause the automated banking machine or other devices to take appropriate programmed steps.

[0108] In still other exemplary embodiments the processor may be in operative connection with an RF emitter. The processor may operate in accordance with its programming to cause the emitter to generate RF signals that interfere with the detected signals. This can be done on a continuing basis or alternatively only at times during user operation of the automated banking machine when user inputs are likely to be intercepted. For example, the processor controlling the emitter may operate the machine or be in communication with a controller thereof. In such situations, the processor may operate to control the emitter to produce outputs at times when a user's card is moving into or out of a card slot, and/or when the machine is accepting a user's PIN or other inputs. Thus, the emitter may be operative to produce interfering signals during relatively brief periods so as to not disrupt RF transmissions for an extended period in the event an incorrect determination is made and the RF signals are from a legitimate source.

[0109] In some embodiments an emitter may be a type that transmits on a plurality of frequencies intended to disrupt transmissions within the expected range of frequencies for a fraud device. In other embodiments the emitter may be controlled responsive to the processor to match the frequency or frequencies of suspect signals that have been detected. Of course these approaches are exemplary of approaches that may be used.

[0110] In the exemplary embodiment, the automated banking machine **10** is provided with enhanced diagnostic capabilities as well as the ability for servicers to more readily perform remedial and preventive maintenance on the machine. This is accomplished in an exemplary embodiment by programming the controller and/or alternatively distributed controllers and processors associated with the transaction function devices, to sense and capture diagnostic data concerning the operation of the various transaction function devices. In an exemplary embodiment this diagnostic data may include more than an indication of a disabling malfunction. In some embodiments and with regard to some transaction function devices, the data may include for example instances of speed, intensity, deflection, vacuum, force, friction, pressure, sound, vibration, wear or other parameters that may be of significance for purposes of detecting conditions that may be developing with regard to the machine and the transaction function devices contained therein. The nature of the diagnostic data that may be obtained will depend on the particular transaction function devices and the capabilities thereof as well as the programming of the controllers within the machine.

[0111] An exemplary arrangement includes an automated banking machine security arrangement. The automated banking machine includes a Global Positioning System (GPS). An automated banking machine with GPS can include self-service features enabling a user of the machine to carry out transactions. As previously discussed, an automated banking machine can include a cash dispenser permitting a cash withdrawal transaction. As explained in more detail later, GPS (or some other position indicator) also enables more efficient servicing of an automated banking machine. Systems and methods related to the monitoring, status, and servicing of automated banking machines may be found in U.S. Pat. No. 5,984,178, the entire disclosure of which is herein incorporated by reference.

[0112] An automated banking machine (or each machine in a network of automated banking machines) can be embedded with a GPS transceiver. The operation of a GPS is well known and need not be discussed in detail herein. A machine's GPS module or unit can identify the geographical position of the machine by using a coordinate system. For example, the GPS unit can read its latitude and longitude coordinates with the use of one or more satellites. A machine with GPS technology allows the machine to annunciate its location. The machine can emit its coordinates through a variety of known communication mechanisms.

[0113] In an exemplary arrangement, an automated banking machine (or component(s) thereof) is provided with GPS to permit tracking of the machine (or component(s) thereof). The tracking can be beneficial in maintaining accurate location information on a plurality of machines, especially if certain machines are moved during their lifetime. As explained in more detail herein, tracking can also be used to thwart thieves who are able to pickup and remove an entire machine unit (or component(s) thereof).

[0114] A GPS unit (including an antenna) can be built into an automated banking machine so that the GPS cannot be dismantled. The GPS can be connected with a machine in a manner ensuring that the machine's positional information (i.e., coordinates) can continue to be conveyed. For example, critical components of the GPS (and machine) can be battery backed to enable conveyance of the unit's position. This arrangement permits a GPS disconnected from its main power source to still have the ability to accurately obtain from one or more satellites the machine position. The GPS unit may comprise a satellite phone.

[0115] An automated banking machine computer or controller can request a reading of location data from the GPS unit. It should be understood that for purposes of brevity, herein a "computer" may comprise one or more computers. The GPS unit can obtain the machine position coordinates from one or more satellites. The machine computer can receive the location data from the GPS unit. The machine can transmit its GPS-obtained position to a service monitoring (or responsible for) the security of the machine. The security monitoring service center may oversee the monitoring of plural GPS-equipped machines. Communication between a machine and the security center (which may be the machine's host) can be carried out in a known manner of communication, including the use of a phone line, a proprietary line, a wireless system, a satellite system, a network, an intranet, and/or the Internet. Critical components in the machine can also be battery backed to ensure communication with the GPS unit and the security center. A computer software program operating at the security center (or in the machine) can be used to determine if the normally stationary (or fixed) machine terminal has been improperly moved.

[0116] FIG. **16** shows a shared security/monitoring arrangement **300** for plural automated banking machines. The arrangement **300** includes a satellite **302**, automated banking machines **304**, **306**, **308** with respective GPS units **310**, **312**, **314**, and a security/monitoring center **316**. As previously discussed, the machines **304**, **306**, **308** can obtain a GPS reading via the satellite **302** and then transmit the read data to the security center **316**. For example, a GPS reading may be obtained with a satellite phone which is able to transmit the GPS data to a web site accessible by the security center computer. The security center **316** can include many different types of communication devices, including a cell phone system **318**.

[0117] A stolen automated banking machine (or one or more components thereof) having GPS technology enables movement of the stolen machine (or the one or more components thereof) to be tracked. One or more computers operating in conjunction with a security center enable the current position of a moving machine to be tracked in real time. Software operating in a security center computer can be used to present the individual GPS-reported machine positions as a simultaneous path of travel. The software can overlay the travel path of a stolen machine onto a road map of the surrounding area. Authorities can be kept informed as to the route of the tracked machine. The real time overlay map can also be downloaded (e.g., via the Internet) from the security center to the authorities (e.g., police). The monitoring arrangement permits a stolen machine with GPS to be recovered.

[0118] The security center can be in operative connection with a database containing the locations of respective automated banking machines stored in memory. The security center can use a computer (e.g., a host computer) to compare a received machine GPS location to the stored location assigned to that particular machine. If the compared locations do not substantially match, then the computer can determine that the machine was stolen and, responsive thereto, cause proper action to be initiated. The comparison may include a predetermined percentage error range to compensate for GPS reading calibrations, fluctuations, deviations, and other factors. Additional GPS location data readings and location comparisons may be performed to ensure accuracy before a final determination on theft is made.

[0119] FIG. **17** shows steps in a process of comparing read GPS location data to stored automated banking machine location data. Location data for a plurality of machines (i.e., machine #**1** to machine #N) is stored in a database **320**. Stored data **322** includes location data corresponding to the fixed or assigned location of machine #**1** (e.g., machine **304**). Stored data **324** includes location data corresponding to the fixed location of machine #**2** (e.g., machine **306**). GPS data **326** was obtained using the GPS unit of machine #**1**. The location data in the stored data **322** for machine #**1** is compared to the GPS location data **326** for machine #**1** by using a computer **328**, which may be in the security center **316**. If the comparison results in a corresponding "Yes" match, then machine #**1** is determined as secure **330**.

[0120] However, if the comparison does not results in a corresponding match, then the security status of machine #**1** is determined as stolen. Following a "No" match, at least one of the response actions **332**, **334**, **336**, **338** can be executed, as explained in more detail later. That is, response to a determination of theft one or more actions can be initiated, including notifying **332** the authorities about the theft, firing **334** dye packs located in the stolen machine, tripping **336** an alarm in the stolen machine, and/or tracking **338** movement of the stolen machine. It should be understood that a security center **316** can include the database **320** and the computer **328**, and cause commencing of the actions **332**, **334**, **336**, **338**. Alternatively, the database **320** can be remotely located from the security center **316**, yet in operative connection therewith to enable the security center to request and receive location data from the database (and store data in the database).

[0121] It should be understood that an automated banking machine can be equipped with one or more GPS units. Different GPS units can be spaced from each other by being arranged at predetermined locations in/on the machine. One or more components or parts of an automated banking machine can be equipped with a GPS unit. For example, but not limited thereto, machine components such as one or more currency cassettes, deposit cassettes, money order paper stock cassettes, divert/retract cassettes, computer elements, display devices, safe, etc. can each have their own GPS unit. Providing individual component parts of a machine with GPS communication ability allows these component parts to be tracked separately to/from the rest of the machine body. Thus, individual machine components (each having one or more GPS units) can be tracked or monitored in the same manner previously described for an entire machine. Thus, a stolen (or missing) component that was separated from the main body of the machine can be tracked for recovery. The ability to track individual machine components also enables secure oversight of currency cassettes (or other valuable machine components) on their journey toward/from a machine. For example, replacement currency assigned for transport to a predetermined machine location can have its travel path monitored via the GPS arrangement to ensure its proper delivery. Each currency cassette in a system of plural currency cassettes can have its location monitored for reasons of status, availability, inventory, etc. The GPS location analysis performed by the security center **316** for a particular automated banking machine can be used to cause the firing of dye packs in that particular machine. FIG. **18** shows the machine **304** including a secure chest or safe portion **340**. The machine chest **340** includes a dye pack **342** adjacent to cash **344** in a currency dispenser **346**. The cash **344** may be in a currency cassette in the currency dispenser **346**. The machine chest **340** also includes a dye pack **348** adjacent to cash **350** in a cash deposit bin **352**. The cash deposit bin **352** can hold cash that was deposited by machine users or cash that was not taken following a cash withdrawal transaction. The GPS transceiver **310** and a machine computer **354** are also shown. The machine computer **354** can cause firing of the dye packs **342**, **348**. The computer **354** can be instructed by the security center **316** to fire the dye packs **342**, **348**. The machine **304** further includes movement sensors **360**, **362**. Although the GPS unit **310** and the machine computer **354** are shown in the upper portion **356** of the machine housing **358**, it should be understood that they may be situated inside of the secure chest portion **340** of the machine housing (e.g., like GPS unit **314**).

[0122] Different communication methods can be used in carrying out the determination of whether a machine was stolen. In one arrangement the machine computer **354** can periodically obtain a regularly time-based location reading from the GPS unit **310** (i.e., predetermined reading times). In another arrangement the machine computer **354** can continuously receive updated GPS data from the GPS unit **310**. The machine **304** (or the GPS unit **310**) can transmit the read GPS location information to the security center **316**. The security center **316** analyzes the transmitted GPS location information (e.g., by performing the previously discussed location comparisons) to determine if inappropriate movement (e.g., theft) involving the machine **304** has occurred. As previously discussed, response actions **332**, **334**, **336**, **338** can also be initiated via the security center **316**.

[0123] In another arrangement the machine **304** can use the sensors **360**, **362** (e.g., motion detectors) to detect movement (e.g., tilt, lateral, vertical, and/or horizontal movement) of the machine **304**. The machine computer **354** is in operative connection with the sensors **360**, **362** to receive information therefrom. In response to a sensed machine movement, the machine computer **354** can take action to thwart the suspected theft of the machine **304**. For example, the computer **354** can cause the dye packs **342**, **348** to be fired. The computer **354** may notify the security center **316** of the sensed machine movement. As previously discussed, the security center **316** can initiate response actions **332**, **334**, **336**, **338** to thwart the suspected theft of the machine.

[0124] Alternatively, an analysis of GPS location information can be used to verify whether or not the sensed machine movement was the result of the machine **304** being illegally moved from its expected location or because of some other disturbance (e.g., an earthquake). In response to a sensor **360**, **362** detecting movement of the machine **304**, the machine computer **354** can request a location reading from the GPS unit **310**. The machine **304** transmits the acquired GPS location data **326** to the computer **328** associated with the security center **316**. Again, the security center **316** can compare (as previously discussed) the GPS location data **326** to stored location data **372** to determine whether the particular machine **304** (i.e., machine #**1**) was actually moved from its foundation. Thus, both movement sensors **360**, **362** and GPS **310** can be used together to accurately determine whether or not a machine **304** was stolen.

[0125] In a further arrangement the plurality of automated banking machines **304**, **306**, **308** each include a wireless cell phone. FIG. **18** shows the machine **304** including a cell phone system **366**. The machine computer **354** is in operative connection with the cell phone **366**. Each machine can use their cell phone to call the security center **316**, which includes the cell phone system **318**. Each machine is also operative to receive calls from the security center **316**. The security center cell phone system **318** is operative to simultaneously communicate with plural machines via their cell phones.

[0126] The security center **316** is in operative connection with a database having memory for storage of cell calling area information corresponding to each respective machine cell phone. The stored cell calling area information can be in previously discussed database **320** or it can be in a separate cell database. FIG. **19** depicts an expanded portion of the database **320** showing additional machine information. The previously discussed stored data **322** corresponding to machine #**1** is also depicted. For machine #**1** the identity data **370** is stored in corresponding relationship with the machine's location data **372**, cell phone number data **374**, and call cell data **376**. The database **320** enables the identity **370** of a machine to be ascertained via its stored location data **372** or by its stored cell phone number data **374**. Likewise, a machine location **372** can be identified via its cell phone number **374**, and vice versa. That is, in the database **320** each machine cell phone number is also stored in corresponding relationship with a respective cell calling area. For example, phone number data **374** is stored in relation with cell data **376**.

[0127] The cell assigned to an automated banking machine can be the call cell in which that machine is physically located. That is, the assigned cell can be the cell in which the cell phone (of the fixed machine) would use to originate a phone call. The stored location data for a particular machine can be used to determine which cell is to be assigned to the phone number for that particular machine. That is, the assigned cell can be based on the stored (and assigned) loca-

tion. For example, the cell calling area which covers the location **372** of machine #**1** can be used as the cell **376** assigned to machine #**1**. Using the stored location data enables the database to be quickly updated to reflect any changes in cell areas, cell providers, etc.

[0128] It should be understood that some automated banking machines may be located in the same cell calling area. Thus, these machines could be assigned the same cell data in the database **320**. For example, both machine #**1** and machine #**3** could have the same stored cell data. Contrarily, a cell in the database may be assigned to only a single cell phone number because the phone number belongs to an isolated distant machine. For example, the cell data assigned to machine #**2** may be the only instance of that cell in the entire database **320**.

[0129] It should be understood that one or more components or parts of an automated banking machine can be equipped with a wireless cell phone. As previously discussed, these machine components may comprise one or more currency cassettes, deposit cassettes, money order paper stock cassettes, divert/retract cassettes, computer elements, display devices, safe, etc. Providing individual component parts of a machine with their own cell phone communication ability allows these component parts to be tracked separately from/to the remainder of the main machine body. Thus, individual machine components (each including one or more cell phones) can be tracked or monitored in the same manner previously described for an entire machine.

[0130] An exemplary security checking operation involving the cell phone arrangement will now be discussed. A machine computer **354** causes the cell phone **366** of a machine (or machine component thereof) to periodically call the security center cell phone system **318**. The security center **316** uses the computer **328** (or another computer) to perform an initial analysis of the received call. In an exemplary embodiment of first level security analysis, the security center **316** can recognize which machine cell phone placed the call, such as by using caller ID, etc. The security center **316** can use this information to learn the cell assigned to the machine from which the call was made. For example, the security center **316** can use caller ID to ascertain the phone number **374** belonging to a call originating from the phone of the not yet identified machine. By knowing the phone number **374** the security center **316** can use the database **320** to identify the machine as machine #**1**. The security center **316** can further use the database **320** to determine the cell **376** assigned to machine #**1**. Thus, the assigned cell **376** is known.

[0131] Next, the security center **316** needs to compare the assigned cell **376** to the used cell. The security center **316** can obtain the cell used by the machine phone. Triangulation calculations or secondary sources may be used in obtaining the cell in which the call was made. The security center computer **328** can then compare the obtained cell to the cell **376** assigned to that particular machine **370**. If the compared cells do not match, then it is determined that the cell phone of machine #**1** was moved out of its assigned cell area **376**. The security level for machine #**1** can be flagged as suspect. Thus, the theft of machine #**1** can be viewed as suspect. In the first level of security analysis, improper movement of a particular machine can be suspected via the machine's cell phone, without using the machine's GPS unit. Although machine #**1** was used in the example, it should be understood that a first analysis can be applied to any of the machines in the machine network.

[0132] Returning to the exemplary example, following a suspicion of theft of machine #**1**, the security center **316** can initiate appropriate response actions **332**, **334**, **336**, **338** to thwart the suspected theft, as previously discussed. Alternatively, in response to the suspicion, the security center **316** can begin another (second) level of security analysis on machine #**1**. That is, a second analysis can be performed before a response action **332**, **334**, **336**, **338** is initiated by the security center **316**. The second analysis can be performed to double check or validate the suspicion of theft of machine #**1**. The second analysis can be independent from the first analysis. The second analysis can use the GPS unit of machine #**1**.

[0133] In an exemplary embodiment of second level security analysis, the security center **316** submits a request to the suspect machine #**1** asking for an updated GPS reading. The request can be communicated in a manner previously discussed, including using cell phone communication. In a manner previously discussed, a machine computer **354** attempts to obtain an updated reading with its GPS unit **310**, and then transmit the updated reading to the security center **316**. The security center **316** can then compare (as previously discussed) the updated GPS location data **326** to database location data **372** corresponding to the suspect machine #**1**. Based on the location comparison, the security center **316** can determine whether the suspected theft activity was founded. If an updated GPS reading is no longer obtainable then this information can also be a factor in the determination. Once a determination is made that the machine was actually illegally moved (i.e., stolen), then responsive actions such as notifying authorities **332**, firing dye packs **334**, starting an alarm **336**, and/or machine tracking **338** can be initiated to thwart the theft.

[0134] In other security arrangements, the machine does not have to rely on a security center to perform a determination of machine movement. In an exemplary embodiment the machine's own computer can make the determination.

[0135] An automated banking machine computer can have a backup battery power source. Battery sources for computers are known in the art. A machine computer **354** can have access to location data locally stored in the machine. For example, the machine data **322** can be stored in machine #**1** or in a security software program operating in machine #**1**. The location data **372** for machine #**1** may have been previously downloaded to machine #**1** for storage therein. Thus, the machine #**1** computer **354** itself (instead of the security center) can run a security computer program to perform a comparison of the machine's assigned location **372** to the location obtained from the machine's GPS reading **326**. If the machine computer **354** determines that the locations **372**, **326** do not match, then the machine computer **354** can cause a machine alarm to trip and/or notify the security center (or other authorities) regarding the theft of the machine. Again, the security center can cause appropriate response actions **332**, **334**, **336**, **338** to be carried out.

[0136] In another security arrangement, motion sensors, GPS, and a cell phone (or cell phone modem) can be used in combination to analyze the status of a machine. For example, a machine GPS unit can periodically or continuously receive position readings. The GPS unit and cell phone are in operative connection so that the cell phone can receive GPS data from the GPS unit (even when the cell phone is in an "off" or sleep condition). Detected motion of the machine (via a motion sensor) causes the cell phone to be placed in an "on" or awakened condition (i.e., turned on). The cell phone when

turned on is programmed to transmit GPS data to a satellite. The satellite can receive the transmitted data and recognize the data sender (i.e., the cell phone/machine). The satellite can then send the GPS information and sender data to a web site that allows monitoring of the machine's location. That is, the web site can be accessible by a security center computer.

[0137] It should be understood that various alternative combinations may be used in the exemplary embodiments. For example, a cell phone can be programmed to receive and transmit the GPS data. A cell phone can include the GPS system. Also, while motion is detected, a cell phone can be periodically turned on (e.g., every minute) to receive and/or transmit the GPS data. When movement of the machine stops, so do the transmissions. Furthermore, the cell phone can bypass the satellite to send the GPS information (and cell phone/machine ID data) directly to the web site (or a database). A computer can link the GPS unit and the cell phone. Alternatively, a GPS satellite phone may be used.

[0138] An automated banking machine's alarm can be tripped responsive to reading GPS data. The alarm can also have a backup battery power source. An alarm controller in the machine can activate the alarm in response to the machine's security computer program determining movement of the machine via the GPS reading (and/or via one or more movement sensors). The alarm can be audible or silent. A silent alarm can notify a security center or authorities. An audible alarm can have different decibel levels. A higher decibel level, which is uncomfortable to a thief operating the getaway vehicle, may be used while machine movement is detected. The alarm can be switched to a lower decibel level when machine movement is no longer detected, or vice versa. Hence, a machine can have a plural stage audible alarm. Furthermore, known functions for drawing attention to a stolen machine or cash may additionally be used. For example, the GPS can also be associated with tripping a cash staining device (e.g., dye packs) located in the machine.

[0139] Other communication devices can also be used in determining the location of an automated banking machine (or one or more components thereof). For example, a machine (or one or more components thereof) can be fitted with one or more radio frequency identification (RFID) tags (or labels or devices or indicator members). The RFID tags can be of any type, including those that operate on an RF backscatter principle. The RFID tags can be passive or active. The RFID tags can be read by RFID tag readers. A tag reader can be used in determining that a particular machine (or one or more components thereof) was near a particular location. Each tag reader can be operatively connected with a computer of a machine security monitoring system. The reading of a tag of a machine can be an indication that the machine was moved. Thus, the reading of a machine tag can cause the proper authorities to be notified that a machine (or component thereof) has been moved (e.g., stolen).

[0140] RFID tag readers can be positioned at predetermined geographic locations, including local and remote locations. For example, RFID tag readers can be locally located in the immediate area surrounding an automated banking machine so that any short distance movement of the machine would be detected. The detection of local (initial) movement of a machine can be useful in quickly notifying authorities during the initial stage of machine theft. Other tag readers can be remotely (further) located from the machine, such as along streets or roads. The detection of travel movement of a machine can be useful in notifying authorities as to the direction of travel of a stolen machine. The detection can aid in tracking the machine.

[0141] In an exemplary embodiment, if a stolen automated banking machine (or component thereof) is taken on a highway near a toll location having an RFID tag reader system such as EZ Pass, then the machine's RFID tag can be read and recorded. The system's record shows that the specific machine tag was detected near a specified location at a specific date and time. The RFID tag detection system can also be programmed to receive data corresponding to a reported stolen machine. The system can check whether a read tag matches a tag of the stolen machine. Upon determination of a match, the system can then automatically provide authorities (e.g., police) with the record for that tag (of the detected stolen machine).

[0142] The RFID tag detection system can also include additional security features. For example, the matching of a stolen tag can cause the tripping of a camera(s) to capture one or more images of the vehicle, license plate, and/or driver, etc. The images can be sent along with the record as a report to the proper authorities. In other system arrangements, upon detection of a reported stolen RFID tag, devices adjacent the vehicle can be activated to impede or prevent further movement of the vehicle. For example, a toll gate can be disabled or tire spikes raised. The system can operate in real time. The detection/monitoring system can include one or more computers and communicate via the Internet or other communication arrangements.

[0143] In a further exemplary embodiment, even if an automated banking machine **304** is stolen, the cash in its chest portion **340** (or safe) can be rendered useless to the thieves. The security system in the machine can also monitor the sequence that was used to open the machine's chest **340**. The security system, which can include the computer **354** and a software program operable in the computer, can recognize a normal (or permitted) chest opening sequence. The security system can also detect a non normal (or non authorized) chest opening sequence. If the chest is not opened in the proper sequence, then the security system can act to have cash **344**, **350** inside the chest **340** marked in a manner indicative of stolen cash (e.g., stained/dyed cash).

[0144] The software can be programmed to monitor of all chest opening sequences. Alternatively, the software can be programmed to initiate monitoring of a chest opening sequence following a detection of suspicious (or confirmed) machine movement.

[0145] An example of a normal sequence for accessing the cash in the chest will now be demonstrated. The predetermined chest door opening sequence can include a plurality of sequence events. In the example, the automated banking machine is first put into a maintenance mode. Next an unlocking of the chest door occurs. This may include entering one or more correct combinations. Next the chest door handle is turned to cause an interior lock bolt to move to unlock the chest door. Then the chest door is pivoted or swung to an open position to provide access to the chest interior. It should be understood that the opening of the chest door may be one of the sequence events. The performing of certain steps in the sequence can be a prerequisite for later steps.

[0146] Sensors can detect whether a predetermined (normal) sequence portion was carried out. The sensors can be in operative connection with the security system computer to provide feedback to the computer. Again, the security system,

including the computer and sensors, can operate with a backup power source, such as one or more batteries.

[0147] The computer can be informed or recognize when the automated banking machine status condition is in maintenance mode. Sensors can be used to detect when unlocking of the chest door occurs. The entering of mechanical or electronic combinations can be sensed. Sensors can detect when the chest door handle is turned. Sensors can be positioned adjacent to the handle to detect movement of the handle. Motion sensors can be positioned adjacent to the lock bolt work components which (in the predetermined sequence) would need to move to permit opening of the chest door. Other sensors can be used to detect when the chest door was moved from a closed position to an open position. An example of a lock bolt work arrangement for an automated banking machine may be found in U.S. Pat. No. 5,784,973, the entire disclosure of which is herein incorporated by reference.

[0148] The software operated by the security system computer can analyze the sensor input to determine if any events or steps in the normal chest door opening sequence have been bypassed. The software can compare the sensed (performed) sequence events to the stored (expected) predetermined sequence steps. For example, the automated banking machine computer can monitor and track sequence event occurrence. Responsive to the monitoring, the computer can determine whether all expected sequence events have occurred. The computer can assign a condition (e.g., positive or negative) to the chest door opening status. Therefore, when opening of the chest door is detected, the computer can conclude whether to fire the dye packs.

[0149] In a non normal chest opening sequence the chest door was opened, but not in the expected sequence. For example, the chest door (or other chest components) may have been drilled or burnt to enable the chest door to be opened for accessing the cash. The exemplary automated banking machine security system can detect if a chest bolt was unlocked without the chest door lock first being unlocked (or other optional prerequisite steps, e.g., maintenance mode, combination, code access, etc.). For example, the security system can detect whether the door combination was not correctly (or ever) entered, yet the chest's interior bolt was moved to an unlocked position. The security system can also detect whether the chest door was opened without turning of the door handle. The security system can make a determination that unauthorized access was granted to the chest interior responsive to the door being opened (or in an unlocked position enabling opening thereof) out of sequence. The detection of a non normal chest door opening sequence (or order) can be interpreted as an attack against the chest (and any cash therein).

[0150] In response to a determination of an attack against the chest, the cash **344**, **350** inside the chest **340** can be devalued by the security system. The chest **340** includes a chest door, such as previously discussed chest door **18**. The chest door in an open position enables a service person to access devices and components in the security chest interior. The security system includes a currency staining system, and a method of actuating the staining system. For example, the security system can include dye packs **342**, **348**. The dye packs **342**, **348** can be located in the chest **340** adjacent to the cash **344**, **350**. The security system can cause the dye packs **342**, **348** to be activated (e.g., fired or exploded) to release the dye therefrom.

[0151] The security software operating in the automated banking machine computer **354** can be programmed to cause the computer **354** to initiate firing of the dye packs **342**, **348** in response to a determination that the door of the chest **340** was opened (or moved) without following (or completion of) a required sequence (or pattern) for opening the chest door. That is, dye packs can be triggered to fire upon unauthorized movement of the chest door. The computer programming software in the security system can be read by the computer **354** to determine unauthorized chest access and initiate an electronic firing of the dye packs.

[0152] The automated banking machine security system computer may determine that the door opening sequence is improper prior to the chest door being opened. Thus, the computer may be programmed to automatically fire the dye packs when the chest door is still closed but is detected as being placed in an unlocked condition. In other programming embodiments firing of the dye packs may not occur until the chest door is actually opened. For example, the computer may not determine an improper sequence until the chest door was actually opened.

[0153] In alternative embodiments the computer can issue a warning of a detected improper chest opening sequence. Such a warning can be audible or visible (e.g., a display message, etc.). The warning may be presented in a manner that is undetectable (silent) to the public, but detectable to an authorized service person. The warning may be presented as a flashing light at the rear of the automated banking machine. The warning may be presented via a cell phone call to a specific number at a security center. The warning may be beneficial to an authorized service person who inadvertently generated an out-of-sequence step. A code can be inputted to the machine to override or reset the out-of-sequence programming, or disable firing of the dye packs. Entry of the code may be time based. For example, if the code is not entered within a predetermined time period, then override is no longer a valid option.

[0154] Dye released from a dye pack **342**, **348** is operative to deface cash (i.e., currency or money or notes or bills) in a known manner. The size and amount of dye packs and their placement relative to cash in a machine chest can be strategically predetermined to ensure optimum devaluing of all the cash in the chest upon activation of the dye packs.

[0155] New automated banking machines can be provided with the sequence monitoring security system. Existing automated banking machines can be retrofit with the security system. Because the sequence monitoring security system can be provided in some machines without needing any additional sensors or alarm grids, it can be easy to provide a low-cost retrofit. The sequence monitoring security system may be provided as a backup to normal anti-theft detection arrangements for machines.

[0156] As previously discussed, an automated banking machine computer can cause dye packs to be fired, such as in response to a security software program detecting an improper chest opening sequence. That is, a machine computer can control operation of the machine dye packs. As previously discussed, a machine computer can also communicate with the security center computer. Thus, the security center can directly communicate instructions to the machine computer, including instructions for the machine computer to fire the dye packs. That is, regardless of the monitored security status of a chest opening sequence, a machine computer can be instructed by a security center to activate the dye packs

at any time. Thus, dye pack activation can be independent of chest opening sequence monitoring.

[0157] As previously discussed, dye pack activation can be a response action **334** to machine theft. A security center **316** can use machine GPS information **326** to confirm that a machine was stolen. Responsive to the confirmation of theft, the security center **316** can instruct the machine computer **354** to actuate its dye packs **344**, **348**. Upon the machine computer **354** receiving the instruction to fire the dye packs **344**, **348**, the machine computer can cause the dye packs to be exploded to stain the cash **344**, **350** located within the interior of its chest **340**. Thus, the staining of money inside of a machine can be the result of a positional reading taken with a GPS unit of that machine.

[0158] In another exemplary arrangement, the security center itself can directly signal machine dye packs to fire. That is, the security center can fire the dye packs without using the machine computer. The security center may cause the dye packs to be activated following a theft confirmation. The signal from the security center to a dye pack may be encrypted. A dye pack can have a trigger device (or a detonator) set to fire upon receiving a predetermined frequency or wave. A radio frequency may be used. The frequency can be unique to a particular dye pack or a series of dye packs in a particular machine. The security center can generate and transmit the frequency. Alternatively, if the security center is too far from the machine, then the security center can cause the machine (or another nearby source) to initiate or generate the triggering frequency.

[0159] It should be understood that the scope for determining whether an automated banking machine was moved is not limited to the embodiments disclosed herein. For example, image recognition, land-based radar, and sound waves can also be used in determining whether a machine was stolen. A camera unit can be fixedly mounted to periodically capture an image of a machine. The camera unit can transmit the image to a security center. The security center can have an original image of the machine stored in a database. The security center can use image recognition software to compare the image received from the camera unit to the image in storage. Likewise, data relating to land based radar and/or sound waves can be used in determination comparisons. If compared data does not match, then an appropriate response action can be initiated by the machine, as previously discussed. Alternatively, one or more additional analyses may be performed to confirm that the machine was actually stolen. The confirmation analyses may include security comparisons already discussed, such as comparisons involving data related to movement sensors, RFID tags, phone cells, and/or machine GPS.

[0160] An automated banking machine may need servicing. Machine servicing may include (but is not limited to) repair (e.g., of components, transaction function devices, lights, belts, electronics, etc.), preventive maintenance, replenishing supplies (e.g., cash, paper, deposit envelopes, coupons, etc.), and/or removing items deposited in the machine (e.g., cash, envelopes, checks, etc.). A machine can provide its location information via GPS to a service center. A machine with GPS provides the service center (which may comprise the security center) the ability to identify the closest service personnel to the machine's location. A dispatching program can operate in a service center computer (or a machine host computer). The machine service center can receive both GPS location information and a service request from a machine. The GPS information and service request may be received in the same transmission packet. The service center can also receive (e.g., via GPS, address input, phone, voice, etc.) the current (or latest) locations of service personnel in the field. The dispatching program can determine which available service person can reach the machine needing service the quickest. The program can match service personnel to service-needing machines for optimum efficiency.

[0161] The dispatching program can also use received machine GPS location information to generate optimal directions for the chosen service person to use to reach the machine. The directions can include the most efficient route. The directions can be transmitted to the service person in a known manner. The dispatching program can also operate in real time with regard to current traffic conditions that may influence the route decisions, and hence the servicer-to-machine matching. Thus, the chosen servicer may not necessarily be the closest servicer in distance. In an exemplary embodiment, the servicer is chosen based on smallest estimated travel time. The use of machine GPS allows a servicer to reach a machine in the quickest manner. The ability to quickly associate the location of a machine needing servicing with the current positions of available service personnel results in a more efficient service dispatch. Machine operating efficiency can be improved.

[0162] In other exemplary embodiments, an automated banking machine can signal what type of servicing is needed. Thus, a servicer may be chosen based on smallest estimated travel time in conjunction with the needed skill level of the service person.

[0163] An automated banking machine with GPS technology also enables the service person to find the exact machine that needs servicing. In some situations a service record provided to a service person may be vague. It may be difficult for the service person to find a machine based on the address location of the machine. For example, a service record may have a machine address listed as that of an immediate area, such as a retail shopping mall. However, a plurality of machines may be located in the shopping mall. It could be difficult for the service person to determine in a timely manner which machine is to be serviced.

[0164] In an exemplary arrangement the particular machine that needs to be serviced can provide its distinguishing exact location information via GPS to the service center which in turn can pass the GPS data to a service person. A GPS information signal (location indicating signal) indicative of the machine's location and a service request signal can be received by the service center. The service center can transmit the machine location data and the service type needed to the service person's hand-held device, which can be part of the service person's navigation system. This arrangement is shown in FIG. **20**. It should be understood that transmitted signals may be modified or translated by other devices before reaching the service center. Hence, a signal sent from a machine may not necessarily be the same signal received by the service center. Therefore, for purposes of this invention, a signal sent from a machine and received by a service center (or a service person's hand-held device) encompasses this situation.

[0165] The service person can use a hand-held GPS signal reading device to ascertain or determine the machine's pinpoint location. The hand-held GPS device may also be a part of a cell phone or a time piece (i.e., watch) equipped with GPS technology that allows an operator thereof to physically match GPS coordinates. That is, when the machine is found

the hand-held GPS read-out device and the machine should have substantially the same GPS location.

[0166] As previously discussed, the hand-held GPS device can be part of a service person's navigation system. For example, the hand-held device can be a GPS-enabled mobile device. The navigation system (including the portable device) can display an electronic map (or portions thereof), including the service area. The system can receive the machine's GPS data from the service center. The navigation system can simultaneously display several locations on the same street map, including the machine location, the service center location, and the current location of the service person. The servicer can use the displayed electronic map to determine the best route to the machine.

[0167] It should be understood that the navigation system can include more than one display device. For example, the service person's vehicle can have a (fixed) display device that displays the locations. The service person's (portable or mobile) hand-held device can likewise displays the locations.

[0168] It should also be understood that a service person's hand-held device can have many features and capabilities. The hand-held device can comprise a mobile device (i.e., phone, PDA, etc.) that can call up and display electronic maps via mapping software, mapping applications, etc. Mobile mapping and location-based services can be used, e.g., mobile mapping using Wi-Fi, geographically indexed databases for mobile operations, wireless geo-aware services for mobile devices (i.e., cell phones), etc. A satellite-based global positioning system can be used to pinpoint a servicer's cell phone or PDA location. Maps can be provided to mobile devices by GPS or mapping cards can be slipped into the devices. The mobile devices can use earth satellite-image, mapping sites, and mash-ups (i.e., maps that have been infused with other information, such as real time traffic information or instant messaging). Automated banking machine servicers can receive graphical maps, job details, and step-by-step directions to the job site on cell phones, PDAs, and other hand-held devices. The mobile devices can store maps for future use. The mapping and direction features enable dispatch and route systems to be enhanced, including real time location and tracking information.

[0169] Automated banking machines can request a need for servicing via a call to a service center (service provider) or on-line, with their address routed to the service center's intranet and then to a map location server via a mapping web service software maintained on the service center's server(s). The map location server can connect real time location information provided from a service person's mobile device with mapping and routing information provided by the mapping service. A service driver's whereabouts (and travel patterns) can be tracked using cellular signals or GPS, e.g., by tracking their mobile devices. This also enables highly mobile service employees to be personally located or contacted, if necessary. The real time location of service vehicles can likewise be tracked and analyzed. A record of the routing data (including traffic time and route duration) can be analyzed to enhance future service call routing and scheduling, including determining (or linking) the best time of day for service travel to the type of particular machine service needed.

[0170] A servicer's mobile device can be used with GPS-based services that use wireless mapping. The mobile devices (e.g., a J2ME-enabled cell phone) can support J2ME, a version of Java 2 with a graphical interface that makes it possible to put color maps on a relatively small screen. The mobile devices also have the capability to support later versions of Java. PDAs can also be used support mapping software, applications, and services.

[0171] Mapping and message capabilities can be combined. A service person (or a service center or another entity) can find maps and directions at a Web site and then have that information sent or downloaded directly to their mobile device (e.g., cell phone). The service company (e.g., service provider) can use group mapping that enables each service person to simultaneously see the location of all the other (in-field) service persons (and the service center) on a (common) electronic map. Wireless mapping applications can be used that integrate instant messaging, such as showing where colleagues are on a map while they talk or text to each other.

[0172] These features enable nearby service personnel to receive or trade automated banking machine components with each other instead of having to return to a service center for the part. The features also enable service personnel in the field to ascertain and contact nearby assistance, especially for machine repairs that require more than one person.

[0173] Access to Web-based maps can be provided through one or more Internet connections, such as via a cellular network or Wi-Fi hot spots. A mobile device (e.g., Wi-Fi enabled PDAs, J2ME-enabled cell phone, smart phones, etc.) can also be used to access and use Web-based 3-D mapping software. Mapping software can also include support for GPS-enabled devices via Bluetooth technology, including enabling service persons to find directions using GPS coordinates. For example, directions to an automated banking machine can be provided responsive to the servicer proving only GPS-based data. A servicer's mobile device can also receive satellite imagery (e.g., Virtual Earth, Google Earth, etc.) and 3-D images of buildings and streets, including zoom-in and zoom-out features.

[0174] It should be understood that a servicer person's mobile device can be equipped with other features, programs, and communication capabilities. It should also be understood that the mobile devices discussed herein encompass those versions that have the capability to support later (newer) versions of mapping and/or direction software and features. Additionally, it should be understood that for purposes of this invention a "hand-held" device need not be specifically carried by hand, but also encompasses those devices that may be located on (or supported by) the body of a service person. For example, a mobile hand-held device may be fitted adjacent to an ear or eye of the service person (e.g., a communications head phone, head gear, ear piece, and/or eye piece).

[0175] An exemplary process of getting information and carrying out a service call will now be presented. The service person activates their mobile device's (e.g., cell phone, PDA, etc.)

[0176] mapping software through an Internet link or a phone call to the service center (or another entity) to get (updated) maps and directions. Using GPS technology, the cell phone connects to a satellite to get the service person's current position (i.e., GPS coordinates of the mobile device). This position is then (automatically) communicated to the cell phone's mapping software. The software loads a map image that corresponds to the service person's GPS coordinates. The electronic map image(s) is displayed on the cell phone's display screen. The service person can additionally enter an address (or identifier) of the particular automated banking machine they want to locate and service. The GPS technology finds the GPS coordinates for that machine's loca-

tion based on the address provided. With the locations of both the service person and the machine, the cell phone's mapping software can build the necessary maps and provide detailed directions to the machine. The maps and directions are displayable on the cell phone's display screen. The service person's current location and the service person's final location (i.e., the location of the machine) can both be simultaneously displayed on the same map layout in real time. As the service person's current location changes, the map is updated to reflect the movement. Thus, a mobile device can get map data; get its GPS coordinates; present a map showing the location of the mobile device thereon; receive machine location data; present a map showing the machine's location thereon responsive to the received machine location data; present a map showing the machine's location and the mobile device's location thereon; and provide map-based directions between the locations.

[0177] The quick locating of the proper machine can thus be achieved during a machine servicing process. As previously discussed, a machine can emit data representative of its location via a signal (e.g., GPS, cell phone, etc.). The emitted signal can be received by a service center or service person (e.g., via a portable hand-held device, phone, computer, reader, sensor, etc.). A service person can then tangibly (physically or in person) locate (access or pinpoint or view) the particular machine that corresponds to the received location data. That is, the service person, based on the received machine location information, can move (or relocate) to a servicing location that is located adjacent or at the machine's location. The service person can then perform a servicing action involving the machine at the servicing location.

[0178] It should be understood that a service center need not receive GPS location data from the machine in order to carry out servicing. A service person's hand-held device can receive a signal having a machine's GPS data directly, instead of receiving the GPS data second-hand from the service center.

[0179] In another arrangement the service center can receive only a service request from an automated banking machine (e.g., via a cell phone, land line phone, network, etc.). The service request can include an identifier (e.g., serial number) of the machine. The service center can then determine (from a data store) the particular location (e.g., GPS coordinates or street address) that corresponds to the received machine identifier. The service center can include the determined machine location information (along with the type of service needed) in the service report to the service person. The servicer can then use the received GPS location information in finding the machine.

[0180] However, as previously discussed, an automated banking machine street address (or even GPS coordinates) may not be enough information for a servicer to pinpoint the particular machine, especially if several machines are grouped together. Further machine information (such as a machine recognition feature) that is available to the service provider while in the service field may be needed to narrow the search for identifying the particular machine.

[0181] As discussed in more detail hereafter, the service person can use a tool (which can be part of the portable hand-held device) that can be programmed to recognize automated banking machines. A machine can emit (along with GPS signals) machine identifying (feature recognition) signals. The tool can receive at least one machine recognition feature signal (along with machine GPS location signals) emitted from the machine. The service person can use this additional machine identifying information to pinpoint the exact machine that requires the requested servicing, even if the machine is near/adjacent to other machines. That is, a machine can provide enough information (e.g., GPS location data and feature identification data) to a service person in the field to enable that particular machine to be distinguished from other nearby machines, even if the machine s have similar GPS location readings.

[0182] An automated banking machine can emit in an identifying signal, one or more data features. Examples include machine features corresponding to its owner, model type, service problem, and functions or devices it includes (e.g., screen type, envelope depository, check imager, note recycler, etc.). An emitted machine identifying signal can be used by a servicer in the field as a location indicating signal to more quickly identify the particular machine needing servicing.

The identifying signals sent from an automated banking machine may be part of a sent

[0183] GPS signal, which in certain embodiments is receivable by both the service center and the service person. Alternatively, identifying signals sent from a machine may only be receivable within a predetermined short range from the machine. When the in-field service person is close enough (e.g., at the machine's address location), then the signal range is within reception of the service person's hand-held device. It should be understood that an identifying signal may also comprise a different communication format from the GPS signal. For example, machine identifying signals may be received by a servicer's hand-held device as images, RFID readings, cell phone communication, wireless networking reception/detection, e-mail, land based radar, sound waves, VoIP, etc.

[0184] An automated banking machine and hand-held device can also have a passive/active secure communication relationship. For example, the servicer's hand-held device can send a request signal to the machine which then causes the machine to emit its feature recognition signal(s). That is, the machine can emit a location identifying feature after first receiving an authorized request therefor. A hand shaking (encryption) protocol may be involved. Thus, the machine and hand-held device can recognize each other's signals.

[0185] FIG. **21** shows an exemplary relationship among an automated banking machine, service center, and a service person's hand-held device. Circle **1** represents a GPS signal that was sent from the machine. Both the service center and the portable device (or another component of the navigation system) can receive the signal (or a modification/translation thereof). Circle **2** represents data that can be sent from the service center and received by the portable device. As previously discussed, the circle **2** data can include location data, identification data, service data, etc. Circle **3** represents automated banking machine feature/identification data that can be sent from the machine and received by the portable device. All of the transmissions and receptions (circles **1**, **2**, and **3**) can be wireless.

[0186] Thus, an exemplary arrangement encompasses a method comprising the steps of: (a) receiving at least one location indicating signal (e.g., GPS signal, identifying signal) from an automated banking machine (e.g., machine); (b) using the at least one location indicating signal received in step (a) to find or locate the machine; and (c) subsequent and/or responsive to step (b), conducting or carrying out a service activity on or at the machine.

[0187] A further method comprises servicing an automated banking machine subsequent to accessing a location corresponding to the machine, responsive to receiving at least one location indicating signal from the machine. Also, a method comprising servicing a machine subsequent to receiving machine locating data in at least one signal from the machine, wherein the at least one signal includes machine location data and machine identification data, wherein the machine location data includes GPS data and the machine identification data includes machine recognition feature data.

[0188] Another method comprises: (a) receiving a service request sent from an automated banking machine; (b) receiving location identification sent from the machine; and (c) servicing the machine responsive to steps (a) and (b). The service request and location identification can be sent at the same time in the same signal, and received at the same location (e.g., service center). Alternatively, the service request and the location identification can be sent at different times in different signals from the machine, and received at different locations by different entities (e.g., service center and service person). The exemplary arrangement also encompasses an apparatus including an automated banking machine, wherein the machine is operative to send (or emit or transmit) at least one signal therefrom, and wherein the at least one signal includes machine location indicating information enabling the machine to be located and/or identified. Wherein the machine comprises a service-needing machine, and wherein the at least one signal includes a service request.

[0189] A further apparatus comprises an automated banking machine including at least one computer and a communication device, wherein the communication device includes a location identifier, wherein the machine is located at a first location, wherein the machine is operative to wirelessly transmit data reflective of the first location via the location identifier, and wherein the location identifier includes at least one GPS component. The machine is also operative to wirelessly transmit data corresponding to an operating status of the machine, wherein the operating status includes information regarding whether the machine needs servicing. The machine is also operative to wirelessly transmit data corresponding to unique machine identity. The apparatus further comprises a service center, wherein the service center is operative to receive location data and operating status data from a plurality of machines including the machine, wherein the service center is operative to send information corresponding to received location data and operating status data to at least one service person. The apparatus further comprises a hand-held device operative to receive identity data emitted from the machine, wherein the data enables the service person to uniquely identify the machine. The hand-held device comprises at least one of a GPS location reader device, an RFID tag reader device, and a mobile (cell) phone.

[0190] Another apparatus comprises an automated banking machine and a portable hand-held device, wherein the machine is positioned at a first location, wherein the machine is operative to emit location information corresponding to the first location and identification information corresponding to identity of the machine, wherein the hand-held device is operative to receive at least one of the location information and the identification information emitted from the machine, and wherein the hand-held device enables an operator thereof to ascertain the machine responsive to receiving the at least one location information and identification information. Wherein the location information comprises GPS information, and wherein the identification information comprises at least one of machine recognition feature and service request data. Wherein the hand-held device enables an operator thereof to pinpoint the machine responsive to receiving the GPS information and at least one of the machine recognition feature and the service request data.

[0191] It should be understood that the use of GPS for servicing applies to both fixed and portable (or movable) automated banking machines. For example, a portable machine may be built into a vehicle that is able to drive to different sporting events, entertainment venues, etc. The portable machine can be used (e.g., cash withdrawal transactions, etc.) by users at the events. Again, the ability to use GPS to quickly analyze or compare the current position of a portable machine with the current positions of available service personnel results in a more efficient service dispatch.

[0192] The previously discussed use of GPS enables an automated banking machine to be installed at any location just by plugging it in. Thus, in alternative embodiments there is no need to keep a database on where machines are located, because GPS tracking keeps the security/service center aware of their location, especially for purposes of servicing.

[0193] The ability to locate a machine's geographical position can also be used to enhance the usage security of other automated transaction machines. An exemplary embodiment combines the signals of a GPS system with a cellular device (e.g., cell phone) to provide information related to the geographical location of the cellular device user. That is, the exemplary embodiment includes the ability to track cell phones using a combination of cellular or GPS/cellular technology. A cell phone can be equipped with a GPS receiver and/or transmitter.

[0194] The exemplary embodiment also includes the ability to obtain the geographical location of an automated transaction machine. As previously discussed, a machine location can be obtained via an embedded GPS device in the machine or a database of machine installation locations. Thus, a machine user's cell phone location can be compared with the machine location to determine if the user is an authorized user.

[0195] The arrangement can be part of a fraud prevention (or security) service to which an automated banking machine cardholder can join. A member in the fraud prevention program grants permission for his cell phone's location to be known to the provider of the security service whenever his account (or one of his accounts) is accessed at a machine. The member provides to the service provider the information (e.g., cell phone number, cell phone provider, contact options, etc.) necessary to set up the service. The service provider program can be provided by a partnership between a financial institution (e.g., bank), a transaction processor host, and one or more cell service providers. Alternatively, the program can be controlled by a sole proprietor.

[0196] Different types of member-selectable contact options are available. For example, the program can be set up to alert a member about a transaction that is being requested on his/her account from an automated banking machine which is not within reasonable proximity to his/her cell phone. The service provider notifies the member via the member's cell phone that a transaction is being requested at a particular machine. Another selectable option can include having the service provider prevent a transaction request from being carried out when the machine location and the member's cell phone location do not substantially correspond.

[0197] An exemplary method of operation of a fraud prevention service will now be explained with reference to FIG. **22**. As shown, the system arrangement **400** includes automated banking machines **402**, **404**, **406**, a machine host **410** in communication with the machines, a cell phone locator system **412** in communication with the host, and a member's cell phone **408**.

[0198] A machine **402** receives user identification data from a customer. The identification data may be received during a transaction request. The identification can be in the form of a name, account number, PIN, or some other information linking a person to an account. The identification can be input or provided by the customer to the machine **402**, such as from a card or a biometric type of input (iris scan, fingerprint, etc.). Alternatively, the identification may be determined from some other customer input or a customer item read by the machine **402**.

[0199] The machine includes at least one data reader that is operable to read (e.g., receive or obtain) data from a data bearing record. The data bearing record can comprise a data storage format such as a card, a mobile device (e.g., mobile phone), a digital wallet, a biometric component (e.g., eye, finger, DNA) of a person, other data storing configurations, etc. The at least one data reader can read user data that is stored physically (e.g., tangible), electrically, magnetically, and/or chemically, etc. The at least one data reader can also use various data communication modes to read user data, including contact communication, bar codes, wireless communication, near field communication (NFC), radio frequency identification (RFID), etc.

[0200] The machine **402** sends the identification data sent to a computer of the host **410**. The host computer can be part of a host system for a machine network. Each of the machines being in communication with the host. The host **410** can communicate with other computers outside of the machine network in carrying out a transaction.

[0201] The host **410** can determine the machine location from a GPS device in the machine **402** or from one or more databases **414** that includes the locations of the machines in the network. The host has access to the database **414**. That is, the machine may provide its ID to the host. The host can compare the machine ID to IDs in the database to ascertain the machine location.

[0202] The host **410** can also determine the cell phone **408** assigned to the received identification data. The database **414** links authorized machine users to their cell phones (and their accounts). For example, the host can compare received account data to account data in the database **414** to ascertain the cell phone assigned to that account.

[0203] The host **410** is in operative communication with a cell phone locator system **412**. The host requests the cell phone locator **412** to provide the location of the cell phone **408**. The cell phone locator **412** receives the host request and determines the current location of the cell phone **408**. The cell phone locator may use cell triangulation. Alternatively, the cell phone locator may use a GPS device in the cell phone. For example, the cell phone may receive a request from the cell phone locator to report its location. The cell phone can find its location using the GPS receiver. The cell phone can then communicate the location data to the cell phone locator using cellular technology. Alternatively, the cell phone may transmit its location to the cell phone locator using (via satellite) GPS technology.

[0204] The host **410** receives the cell phone location from cell phone locator **412**. The host can then compare the cell phone location to the machine location. If the locations correspond (within a predetermined degree or distance), then the received user identification data is authenticated. The current machine customer (adjacent to the machine) is determined as an authorized user of the account. The transaction request is approved.

[0205] Alternatively, if the locations do not correspond, then the current automated banking machine customer is denied the ability to perform transactions with that account (corresponding to the received identification data). That is, a transaction request would be denied.

[0206] An exemplary example of fraud prevention will now be explained. A person uses an automated banking machine to request a financial transaction, such as a cash withdrawal transaction request for $100 from a checking account. The request (along with other information) is transmitted from the machine to the transaction processor host (which may be the host computer for the machine network). As previously discussed, the host knows or can determine the location of the machine from which the transaction request is being made. The host also knows that the transaction request is from a particular individual due to the identification (e.g., an account number on a card) provided to the machine during the request.

[0207] The host analyzes database records corresponding to that particular individual. The host can determine whether the individual is a member of the fraud prevention program. If so, then the host also determines the member's cell phone provider. The host requests the current location of the member's cell phone from the cell phone provider (or a phone location server associated therewith). The cell phone provider determines the current location of the member's cell phone and then transmits that location back to the host. The host compares the received cell phone location to the machine location. If the two locations are within a predetermined range or proximity of one another then the transaction requested is determined safe and can be authorized according to normal transaction authorization rules in place. However, if the two locations are not in accordance, then appropriate fraud notification rules and procedures can be implemented.

[0208] Thus, grant/denial of a machine transaction request involving a member's account can be based on that member's location. If it is concluded that the member is adjacent the machine, then the transaction request is granted. Otherwise the transaction request is denied. The member's determined location (via the member's cell phone location) can be used as another (or secondary) source of identification.

[0209] A variety of fraud notification rules can be defined (selected) by the member, such as at the time of service protection enrollment. In a first example, if a member has sole access to his account and he normally has his cell phone with him, then he may have selected an option in which the service provider (e.g., bank or host operating on behalf) denies any transaction request where there is a mismatch between the automated banking machine location and his cell phone location. With this selected option the member's cell phone may receive from the service provider a text message like "A transaction was just attempted against your account, but was denied due to location discrepancies between the machine in question and your cell phone. Please contact us at . . . for more information."

[0210] In a second example, a member may share access to an account (such as with a spouse) and it can sometimes

happen that his cell phone location and an automated banking machine location may not coincide. Therefore, the member may select a notification option which causes the service provider to notify him of a requested transaction via a text message on his mobile device (phone), e.g., "A transaction was just requested against your account at the machine located at Wisconsin and M streets." If the location and/or timing of the requested machine transaction is suspicious to the member then he can further investigate. For example, he may call his spouse for verification. If necessary, he can notify the machine's bank and/or the police. Thus, the scenario is cardholder/fraud prevention-centric.

[0211] It should be understood that there are many other detection and notification options available. In the first example an automated banking machine may be instructed by a host to capture the inserted card responsive to a determined mismatch of locations. Further, the host itself may be programmed to notify the police of a potential theft in progress at the particular machine.

[0212] Also, more than one cell phone can be assigned to an account. Thus, the host can obtain the current location of plural cell phones. If the host (or another computer of the service provider) determines that one of the cell phones is currently located adjacent to the automated banking machine then the transaction request is permitted. This option enables both spouses (who have respective cell phones) to separately carry out a machine transaction without requiring service provider notification.

[0213] Other methods of communicating between the service provider and the member may be used. For example, a personal (human voice) phone call may be made on behalf of the service provider notifying the service member of the situation involving their account. IM (instant messaging) may be the communications format used to contact the member's cell phone. Other communication formats can be used.

[0214] Alternatively, a member's device other than their cell phone may be contacted by the service provider. For example, a notifying e-mail may be sent (by the service provider) to the member's home PC. A voice message may be left on the member's home answering machine.

[0215] As discussed, different security levels of fraud detection and member notification can be selected by the member. For example, a different level of detection may use cell triangulation in placing the location of a cell phone instead of having GPS embedded in the cell phone. The cell in which the cell phone is deemed present can be compared to the cell in which the automated banking machine resides. If the cells correspond, then the transaction requester is authenticated as an authorized user of the account. It should be understood that even further detection and notification procedures are available to members of the security system.

[0216] As previously discussed, an exemplary embodiment of the security system enables authorization (or authentication) of automated banking machine transactions based on the (cellular) location of the security system member. The authorization can be further based on GPS location of the machine. The exemplary security system provides additional transaction security to help prevent unauthorized machine access to a financial account if it is determined that the location of the machine from which the account transaction is being requested substantially differs from the location of the authorized user of the account. The location of the machine can be determined via GPS technology. The location of the authorized user can be determined via the location of the user's cell phone. The location of the cell phone can be determined via cellular or GPS/cellular technology.

[0217] It should be understood that the description of the security system with regard to automated banking machines is exemplary, but is not to be limited thereto. An automated banking machine is one of many automated transaction machines in which the security system can be implemented. Likewise, the security system can be used with gas stations. A positive comparison of the gas station (or fuel pump) location with the purchaser's cell phone location grants access to the fuel. Alternatively, a cell phone may be located in a vehicle. When a person requests fuel for the vehicle, a comparison is made of the vehicle and gas station locations. Additionally, the security system can be used in conjunction with other transaction facilities, including stores, restaurants, etc. The security system can also be used where location-based identification of a person is needed.

[0218] The ability to locate an automated banking machine's geographical position can also be used to provide location-oriented services to the public. A service provider ("SP") can provide the services. The service provider can comprise or be associated with a previously discussed security center or service center. A computer in the machine (or the GPS system) can convey coordinate location data to the service provider. The service provider can store this machine location data in a database along with other location data corresponding to other machines. Thus, the database can include the locations of plural automated banking machines, including machines belonging to different banking networks. The database may also contain location information for many other locations that may be of public or private interest. The database may contain waypoint location information, e.g., stores, food establishments, bank branches, or even dynamic machine-service vehicle locations.

[0219] Automated banking machines with GPS provide the capability to reference coordinates for machine-based map generation. The database can also store map data. A service provider can use a geographical starting point reference from which to generate a variety of "how to get there from here" directions, which may be in the form of a map.

[0220] An automated banking machine direction-providing service can receive a request for directions from one or more entities (e.g., a person, computer, machine, etc.). For example, a person at a first location (e.g., a merchant store, fuel station, restaurant, etc.) may wish to have directions to the nearest machine. The direction requester may be a person desiring to use a machine to perform a financial transaction (e.g., cash withdrawal, reload a smart card, etc.). The individual may also be a machine service person needing to located a malfunctioning machine.

[0221] The system allows a person to provide their current (or best known) location to the service provider. The current location may be provided to the service provider in numerous known ways. From this "current location" information, the location service can instruct or provide directions to the person on how to get to the nearest (or desired) automated banking machine. The service provider can also provide directions to the nearest machine belonging to a requested particular bank or financial institution (e.g., a bank belonging to the requester's home banking network).

[0222] The service provider providing the directions can comprise a company, person, computer, and/or machine. The service provider can communicate with a direction requester via diverse communication devices and processes. The direc-

tion-providing service can be made available to a direction requester via a variety of communication devices, such as PDA, cell phone, Internet, address input, input device equipped with a GPS receiver, on-line devices, and off-line devices. Other known transmission processes involved in communication may be used, including analog, digital, wireless, radio wave, microwave, satellite, and Internet communication. For example, the service provider may use a computer to communicate with a person via voice recognition software and speech software. In another example, a person can wirelessly transmit their request along with their current GPS location to the direction-providing service over the Internet via a hand-held computer. In response, the service can download (e.g., as e-mail, PDF file, voice mail, instant message, etc.) the requested directions (e.g., a detailed map) to the hand-held computer. In a further example, a cell phone can include a GPS system. The person can wirelessly transmit their request along with their current GPS location to the service via the cell phone. For example, when the cell phone calls a particular phone number of the service provider for a directions request, the cell phone also transmits its current GPS location. Alternatively, the service provider can recognize the cell phone number via caller ID, match the cell phone's number to the cell phone's GPS system, obtain the cell phone's current location from the cell phone's GPS system, and then transmit directions to the nearest automated banking machine based on the cell phone's location.

[0223] FIG. **23** shows a service provider **380** in operative connection with a database **390**. The service provider **380** includes at least one computer **382**. The service provider **380** can simultaneously communicate with and provide information to plural requesters **384**, **386**, **388**.

[0224] The database **390** can store automated banking machine location data **392**, map data **394**, and additional data **396**. Such additional data **396** may be key words or phrases, such as landmark names, points of interest, street intersections, city sections such as Chinatown and Little Italy, etc. For example, a requester may not know their exact address location but can inform the service provider (via their phone) that they are near the intersection of 19th and M streets. The computer **382** can recognize (such as via voice recognition software) the received intersection as location information. From the intersection information the computer **382** can provide the requested directions. It should be understood that directions can also contain landmarks, points of interest, street intersections, etc. For example, by knowing which intersection the requester is near and the (real time) visual lay out of the city, the service provider **380** can instruct the requester that the nearest automated banking machine is next to a landmark that is easily visible from the intersection. Such a landmark may be a well lit (neon) sign, a bell tower, a pedestrian bridge, etc. Thus, additional stored data **396** can be used by the service provider computer **382** to more accurately understand requests and provide locations/directions to requesters.

[0225] An exemplary flowchart of requesting/receiving service is shown in FIG. **24**. The actions performed by the requester and by the service provider are also shown. In the exemplary method a requester (e.g., a person) contacts the service provider.

[0226] The SP acknowledges the contact and asks for the person's PIN or service access code. The person provides their PIN.

[0227] The SP compares the PIN with a list of valid PINs and determines the PIN acceptable. The level of service associated with the PIN is obtained. The SP asks for the person's current location. The person notifies the SP of their current location (e.g., an address, notable landmark, etc.).

[0228] The SP analyzes (e.g., voice recognition, speech to data interpretation, etc.) the provided location for best fit location comprehension. That is, the SP computer tries to recognize the provided location. The comprehended location may be compared to locations in the database to determine if it is a usable (valid) location. If the provided location is not usable, then the SP may ask the person to again provide the location, or more information may be requested to ensure location accuracy. For example, the SP may speak the comprehended location to the person and ask the person to validate whether the location is correct. Once a provided location is deemed valid, then the SP can ask for the person's request. In response, the person may request directions to the nearest available automated banking machine.

[0229] The SP uses the database information to determine the shortest available route from the person's current location to the nearest automated banking machine. The SP generates directions in a format capable of being received by the person. The format can match the format in which the request was received. For example, if the request was made via the person's cell phone, then the directions can be provided in a form capable of being received by the person's cell phone. The SP provides the directions to the person. The person receives the directions. It should be understood that in other arrangements greater or fewer steps may be carried out, and the order of the steps can vary.

[0230] The person's request for directions may be selected from a list of options. For example, options may include press number **1** for information regarding the nearest automated banking machine, press number **2** for information regarding the nearest fee-free automated banking machine, etc. Once the first option is input then another set of options may be provided to the person. The second set of options may relate to the context in which the information content is to be provided. For example, assuming that the nearest machine was selected in the first option set, the second options may include press number **1** for the machine address, press number **2** for a map to the machine, press number **3** for an operator to guide you to the machine, etc. Further sets of options may follow to ensure the desired service. The service provider can know the level of service available to the requester based on the provided PIN Likewise, other information (e.g., requester's home banking network) can correspond to the provided PIN.

[0231] The person's communication device may partake in obtaining the person's current location and in notifying the service of the current location. For example, the person's communication device may include GPS. The triangulation of cell areas may further be used to determine the requester's (cell phone) location. Also, a person's request for directions may be a default request based on the manner of communication. For example, a service provider may treat any person calling their phone number as a direction requester by default. Thus, a person may not have to actually (e.g., verbally) request directions, it already being inferred.

[0232] The direction-providing service may be a free service, a pay-as-you-use service, and/or limited to paid subscribers. A person may have access to the service as a result of being a valued customer of a particular bank. For example, an automated banking machine customer that regularly incurs

machine transaction fees to the bank may receive free access to the machine-directing service. The bank can provide (or pay for) the service on behalf of the valued customer.

[0233] The level of service may vary with the type of service to which the person has subscribed. For example, one type of service may include having a personal assistant stay on a phone with the person until they correctly and safely reach their desired automated banking machine, while another level of service may simply provide the street address of the nearest machine.

[0234] Automated banking machines can also be programmed to offer other types of service. A machine can be connected to a commercial response system that provides a fee based information service to the general public. The machine can be equipped with a GPS device and a cell phone. The service provided through a machine can be similar to the service provided through a vehicle via an on-board "On Star" system.

[0235] An exemplary automated banking machine can accept cash or financial cards for service payment (e.g., bank card, credit cards, debit cards, smart card, etc.). Other user verification information may also need to be provided to the machine. For example, use of a debit card may also require input of a PIN. The machine's host and/or another financial entity can analyze the received payment (or billing) information to determine whether the requester (machine user) should be granted access to the information service provided through the machine. After the inputted payment information is deemed acceptable, then the information service can appear as a selectable transaction option on the machine's display screen. The service can include providing information, whether provided to the machine user or provided (on behalf of the user) to another entity (e.g., AAA, police). The service provider can be affiliated with the machine or an independent third party service provider.

[0236] A person can use the information service to obtain (or report) information regarding an emergency. Alternatively, the service can be used by people for non emergencies, such as getting directions. The information service enables an automated banking machine user to communicate live with a person (operator) employed by the service provider. The operator may be located at a call center. The operator can have access to information databases, including the Internet.

[0237] The automated banking machine can have one or more speakers and microphones enabling the user to communicate with the operator. The communication can be two-way through a cell phone in the machine. For example, in response to a service request from a user, the machine's cell phone can initiate a call to the service provider to establish communication between the user and the operator. The GPS location of the machine can be provided to the operator (or the operator's workstation computer) in the initial call. In a manner previously discussed, the machine computer can obtain an updated reading from the machine's GPS system prior to sending the GPS data to the operator. Information (e.g., directions) that is based on the location of the machine (and the machine user) can then be provided from the service provider operator to the machine user. In an exemplary embodiment the service provider can cause the machine to print or display the requested information.

[0238] In an exemplary embodiment the service provider can find and then transmit the GPS coordinates of a requested facility (e.g., restaurant) to a user's GPS (mapping) device. The user's GPS device can simultaneously output (display) its current GPS location and the facility's GPS location in map format. Thus, the user can use their electronic map to find the facility.

[0239] It should be understood that other methods of determining the automated banking machine location can be used. For example, a machine can be without GPS. The service provider can have a database that corresponds the phone numbers of machines with their respective locations. The service provider computer can use caller ID to identify the machine from which the call was placed. The service provider computer can then use the database to determine the machine's location based on the machine's phone number. Cellular triangulation is another method that can be used by the service provider computer to determine the location of the machine from which the call was placed.

[0240] An automated banking machine without a speaker can also be used to provide the service. For example, user and operator communication can comprise text messaging. The user can type text that can be read by the operator. Alternatively, the machine can have text-to-speech software along with a microphone. Speech queries from the user are picked up by the microphone and get converted to text, which is sent to the service provider operator. The operator's station can present the text on a display screen, or can reconvert the text back into speech that is hearable by the operator. Statements made by the operator can likewise be converted to text, which is displayed on the machine's display screen.

[0241] It should be understood that additional known communication formats can be used to enable communication between a machine user and a service provider operator, including Internet communication. It should also be understood that the machines used to provide the information service can be portable, including vehicle mounted machines. Thus, the GPS location of the machine may change. In other embodiments a 911 type of emergency call may be provided as a free service to the public.

[0242] FIG. **25** shows an automated banking machine that is equipped to provide the information service to a customer thereof. The machine can use a (cell) phone to communicate with a service provider call center having one or more computers. The call center can receive the initial phone call from the machine (as represented by the one-way arrow). The machine's location information (e.g., GPS data) can be transmitted to the call center in the initial phone call. Thereafter, the machine phone and the call center phone enable two-way voice conversations between the requester and provider (as represented by the two-way arrow). An operator at (or in communication with) the call center has access to information databases, including map data. The map data can include the names and addresses of all structures in the immediate area of the machine from which the request was made.

[0243] FIG. **26** shows an automated banking machine and operator workstation relationship. Voice communication can occur between the requestor and the operator. The workstation (or a computer associated therewith) can receive the initial phone call from the machine. The workstation can use caller ID to determine the machine's phone number. The workstation can then determine the machine's location from the phone number via use of a database. Once the location of the caller (machine user) is known, then the operator can assist the caller with regard to location-based information. Of course it should be understood that not information that can be provided from an operator to a user has to be based on the location of the machine. For example, airline flight informa-

tion may be requested. However, knowing the machine's location when receiving a user's request can be beneficial in quickly providing the requested information or service, especially in an emergency.

[0244] FIG. **27** shows another automated banking machine and operator workstation relationship. The ability to communicate audibly between the customer and operator is absent. Communication is limited to typing text and displaying the text messages on respective display screens at the machine and workstation.

[0245] FIG. **28** shows a further automated banking machine and operator workstation relationship. The arrangement is similar to that shown in FIG. **26**. Communication is still received as a displayed text message. However, with speech-to-text conversion software the need to type is eliminated.

[0246] It should be understood that other known communication formats between an automated banking machine and a service center/workstation/operator can be implemented in carrying out the discussed information service through a machine.

[0247] An exemplary method comprises: receiving at least one customer payment input with at least one input device of an automated banking machine, wherein the payment input corresponds to a service provider fee; receiving at least one customer request input with the at least one input device, wherein the customer request input corresponds to a requested service from a service provider; and communicating the requested service from the machine to the service provider. The method further comprises receiving the requested service at the service provider remotely located from the machine, and performing the requested service, wherein performing the requested service includes communicating information through at least one output device of the machine. The method further comprises the at least one input device including a card reader and a microphone, and the at least one output device includes at least one speaker.

[0248] An exemplary method of providing information service comprises: receiving at a service provider at least one automated banking machine user communication via a machine cell phone, and wherein the at least one communication includes a machine user request for personal service from the service provider; providing the service requested responsive to the request; and accessing a fee for the service. The at least one communication further includes GPS data representative of the location of the machine. The method further comprises receiving the at least one machine user communication at a call center. The method further comprises providing the service requested via a human operator at the call center, wherein the operator performs voice communication with the machine user. Wherein the method comprises providing requested information during the voice communication. Wherein the method comprises providing the service requested via communication between the service center and another entity.

[0249] In still other embodiments, certain principles previously described can be used in connection with automated banking machines and systems to facilitate the ability to receive cash in exchange for a check. Many people prefer to conduct transactions in cash for numerous reasons. Cash has the benefit of being accepted without the need for the operation of computer systems and devices. Cash is also useful in that it is not generally traceable as it moves from one person to another. The use of cash is also a necessity for persons who do not have financial (bank) accounts or who do not wish to use their accounts in connection with certain transactions.

[0250] FIG. **29** shows a system arrangement that represents an exemplary approach in which checks can be more readily redeemed for cash at automated banking machines. In the exemplary embodiment, checks are enabled to be redeemed for cash without the need for a machine user to provide inputs to the machine that directly correlate to the personal identity of the user presenting the check or the user's account. The exemplary system arrangement further enables a person who is presented with a check to verify (before accepting the check) that the check will be honored for the check amount. In this way the recipient of the check can minimize the risk that the check will be dishonored or invalid.

[0251] The exemplary system arrangement shown in FIG. **29** includes one or more automated banking machines represented **198**, **200**. In the exemplary embodiment, the machines are of the type previously described and can include a display for providing user instructions. The machines can also include at least one input device such as a card reader, a key pad, function keys, and a touchscreen. Machines of an exemplary embodiment also include a check reader which comprises a check imaging device of the type that is operative to receive a check and produce image data corresponding to visual appearance of the check. The exemplary machines also include at least one cash dispenser that is selectively operative to dispense currency to users of the machine. Each machine is also associated with (e.g., includes) at least one processor that is in operative connection with devices of the machine and that operates in accordance with programming to enable the machine to carry out transactions. In the exemplary embodiment, the machines may operate to provide cash dispensing transactions (e.g., a cash withdrawal transaction), check and/or cash deposit accepting transactions, delivery of digital information transactions, fund transfers between accounts, or other types of transactions of the types previously discussed, as well as the check cashing transactions of the types described hereafter.

[0252] The exemplary system arrangement shown in FIG. **29** also includes a service provider system **196**, which may also be referred to herein as a computer system. The computer system **196** includes at least one computer **204**, at least one data store **206**, and at least one consumer interface arrangement **208**. The automated banking machines **198** and **200** are operatively connected through a network **202** to the computer system **196**. It should be understood that although only one computer **204** is shown in FIG. **29**, the computer system **196** may comprise a plurality of computers and/or servers. The at least one computer **204** is in operative connection with the at least one data store **206**.

[0253] As discussed in more detail later, FIG. **29** also shows each of a land line communication device **210**, mobile communication devices **212**, **214**, a wireless communications system **216**, a computer network **218**, a remote computer **220**, a digital camera **222**, and a check **224**.

[0254] In an exemplary embodiment the computer **204** is remotely located from each automated banking machine **198**, **200**. The at least one computer ("computer") **204** can include a financial account computer such as one operated by a bank or other institution that tracks financial accounts for users. For example in some embodiments, the computer **204** is operatively connected to an accounting system that tracks user accounts such as checking accounts, and maintains data related to such accounts, including the balances therein, in the

at least one data store ("data store") **206**. In the exemplary embodiment, the computer **204** is operative to communicate with the automated banking machines **198**, **200** to cause the machines to carry out transactions. Of course it should be understood that while only two automated banking machines are shown, other embodiments can include any number of such machines.

[0255] In an exemplary embodiment the at least one consumer interface arrangement **208** is operative to receive communications from account holders whose data is accessible through the computer **204**. For brevity, the at least one consumer interface arrangement **208** may simply be referred to herein as a consumer interface device, a consumer interface, or an interface device. The interface device **208** is also operative to carry out communications with such account holders. In addition, the interface device **208** can communicate with persons who may be holding coded checks (or potential check recipients) for which check data has been stored in the data store **206**.

[0256] In some exemplary embodiments, interface device **208** includes a telephonic interactive voice response (IVR) device. The IVR device is operative to receive inputs from users by phone, including phones connected via a land line **210**. The IVR device is also operative to communicate with mobile (portable) communication devices which can wirelessly communicate through a communications system, such as the cell phone system or network schematically indicated **216**. The IVR device is also operative to communicate with other wireless communications methodologies. The mobile communication devices can comprise a cell phone (e.g., a smart phone) **212**, personal digital assistants (PDAs) **214**, another wireless device, etc.

[0257] In an exemplary embodiment the consumer interface device **208** is operative to receive inputs from users in the form of telephonic key presses. Software operating in the computer **204** can provide audible outputs in the form of simulated voice outputs to provide users with prompts and outputs through audible messages. Users can provide key press inputs through phones, PDAs, or other devices in response thereto. In other exemplary embodiments, the computer **204** may include voice analysis software. Such voice analysis software may enable users to provide spoken audible inputs that can be interpreted through operation of the computer. The computer may then operate to provide audible outputs to users. Of course these approaches are exemplary.

[0258] In other embodiments, the consumer interface device **208** includes a text messaging device. Such a messaging device provides the ability to communicate text messaging capabilities with cell phones, PDAs, or other devices. Alternatively or in addition, the consumer interface device **208** may provide text messaging capabilities (or other data) through a network **218** with remote computers **220** or other devices. In this exemplary embodiment, the consumer interface device can receive inputs in the form of text messages and also provide outputs to users in such form. Of course these approaches are exemplary.

[0259] In still other exemplary embodiments, the consumer interface device **208** is in operative connection with a web interface. The web interface can provide communications through a wide area network such as the Internet, or through other public or private networks. The web interface can enable the interface device **208** to communicate through HTTP messages, HTML messages, and other types of messages, with remote devices to receive inputs and provide outputs.

[0260] In some exemplary embodiments, the web interface enables the interface device **208** to receive messages including image data corresponding to an image of a check. The computer **204** can operate computer programs that enable analysis of received check image data (e.g., one or more check images) to determine check identifying data, amount data, or other values based on the check image data. The computer can analyze check image data generated through a digital camera **222** which data has been downloaded via a personal computer or other device. Similarly, camera phones or other image capture devices can be used to capture check image data to provide to the interface device to facilitate the carrying out of transactions, as later discussed. Of course these approaches are exemplary, and in other embodiments other approaches may be used.

[0261] In an exemplary embodiment an account holder, who is associated with a financial account such as a checking account, prepares a check (such as check **224**). The check **224** is drawn on the account holder's account. The account holder may alternatively be referred to herein as the maker of the check (or the check maker or payor). The check **224** may be a standard bank check (e.g., a personal check), and in other embodiments may be a special check or other type of instrument that is suitable for use with the particular system arrangement.

[0262] The exemplary arrangement allows the check maker to write a check payable to a person who does not have a checking account. Alternatively, the check maker can write a check to a person who would prefer to receive cash instead of a conventional check. Further, in some cases a potential check recipient may require the check maker to make the check payable to "cash".

[0263] In some situations, such as transaction environments where the recipient has no prior or continuing relationship with the check maker, the recipient may be reluctant to accept a check therefrom. This is because the check may not be backed by sufficient funds in the checking account. Further, in some cases the potential check recipient may have a concern that even if there are sufficient funds in a maker's account at the time of receiving the check, by the time the check is cashed the funds in the maker's account may be depleted so that the check can no longer be honored (not valid).

[0264] Some exemplary embodiments can address these issues by being able to assure a potential check recipient that the funds represented by the check are available and guaranteed. The check maker can provide proof to a check recipient that funds for the check are reserved for cashing of the check. Further exemplary embodiments provide that the check recipient can receive cash in exchange for the check without the need for the recipient to have a financial account or for the recipient to personally identify themselves in order to cash the check.

[0265] In an exemplary embodiment, the check maker can use the computer system **196** to cause a check to be linked/correlated to certification data which verifies that the check is as good as cash. The check maker can use a phone or other device to communicate with the consumer interface **208** to register the check. The check maker transmits data to the interface device **208**.

[0266] In an exemplary embodiment, the check maker first communicates, responsive to prompt messages, data which identifies the maker as a person who is authorized to use the computer system to certify checks. This identifying data can include, for example, the user's name, a secret code, certain passwords, other identification data or combinations thereof. The computer **204** in response to data stored in the data store **206** is operative to identify the person contacting the system as an authorized account holder who is authorized to have their checks certified.

[0267] In the exemplary embodiment, once the computer **204** has verified that the account holder contacting the system is an authorized user, the account holder provides information to the service provider system **196** which identifies the check that is to be guaranteed. This check identifying data may include data from the check, such as the check number. Alternatively or in addition, the identifying data may include all or a selected portion of the micr line included on the check. In still other embodiments, other data may be provided which is usable to identify the check. As can be appreciated, the user may provide this information through key inputs, audible inputs, text inputs, or other inputs as appropriate for the particular type of user device.

[0268] In the exemplary embodiment, the check maker also provides data corresponding to the amount of the check to the interface device **208**. The maker may provide this amount data via numerical inputs, such as through a phone or computer. The check maker may provide all of the necessary check data on-site of a payment or purchase, e.g., just before use of the check.

[0269] In some embodiments the check maker may identify the check by providing a visual image of the check to the computer system **196**. This may be done, for example, through a digital picture taken with a camera, a portable phone (having a camera), or other image capture device. The check amount can be included in the image data (e.g., an electronic image of the check). The check image may or may not yet have the signature of the check maker. Thus, a check can be reserved before it becomes legally valid for cashing by another person. Of course this approach is exemplary.

[0270] After image data corresponding to a visual image of a check is presented to the computer system **196**, the computer **204** can obtain the necessary check data from the received check image data. The computer **204** is configured to operate software that is capable of identifying characters included in the check image data. In this way the computer **204** is able to resolve (or parse) check identifying data such as micr line data, check number data, check amount data, and/or other data from the check image data. The computer **204** is able to determine the check amount from the courtesy amount and/or the legal amount associated with the check image data. Of course different approaches for obtaining check data may be taken in other embodiments.

[0271] After receiving check identifying data, the check amount data, as well as other data that may be required by the computer system **196**, the computer **204** is operative to determine if the account holder's account has sufficient funds to pay the check amount. If the computer determines that the funds are not available, the computer causes the consumer interface device to notify the account holder that the account has insufficient funds.

[0272] If the account holder has sufficient funds to pay the check amount, then the computer **204** operates in accordance with its programming to generate certification (code) data. This certification data in the exemplary embodiment generally comprises a unique code. The code can comprise a unique alphanumeric or other type of code which can be used in conjunction with the check to verify that the check is good. The code can be based on (or an algorithm of) one or more data obtained from the check, e.g., amount, account number, date, etc. The code may also include a factor of a random number. Alternatively, the code may be provided (selected) by the check maker. The computer **204** causes the certification data to be correlated in the data store **206** with the check data.

[0273] In an exemplary embodiment, the system allows the check maker to certify a check before the payee ("cash" or a particular entity) is indicated (written) on the check. Also, in an exemplary embodiment the system prevents a check maker from canceling a certified/coded (reserved) check before the check is used (e.g., deposited, cashed) by the check recipient. This prevents an unscrupulous check maker from giving a coded check to a recipient for payment, and then quickly canceling the check before its use. Thus, the system provides protection to the check recipient.

[0274] A coded check may be completed upon the check maker indicating (writing) the payee to the check. The payee may be "cash" or a particular entity, such as the name of check recipient. A check recipient may change their mind regarding accepting a coded check after the check was completed by the check maker. Also, a coded check may be prematurely completed.

[0275] If a completed coded check that indicates "cash" in the payee field is not accepted by a potential check recipient, then the check maker can easily deposit the check back into their own account or exchange the check for cash. Thus, the system allows a coded check that is made out to "cash" to be deemed to be as good as cash (e.g., currency bills) itself. Hence, the system also provides protection to the check maker in such scenarios.

[0276] If a completed coded check indicating a person's name as the payee is not accepted by a potential check recipient, then the check maker can still exchange the check for cash at an automated banking machine, as discussed hereafter in more detail. It does not matter if the payee section of the check is made out to a name or to "cash", the check can still be cashed at automated banking machine using the code. Hence, the system again protects the check maker.

[0277] In some embodiments a completed coded check (which lists a person as the payee) can be canceled by the check maker. However, the check maker may have to physically bring the check to a teller of a financial institution (e.g., a bank) associated with the system. Upon the teller verifying that the check maker is the actual holder of (in possession of) the check, the teller can cause the correlated check data to be canceled from the system's data store. The cancellation can result in the teller releasing to the check maker the reserved funds that were held for the check amount. A predetermined time period may be required before a person can request cancellation of a particular coded check Likewise, the system may not allow the person (check maker) to receive the reserved funds until after a set time period following a request for check cancellation.

[0278] In the exemplary embodiment, the certification data (code) allows a check recipient to cash the check at an automated banking machine that is associated with the system. As previously noted, a coded check can be redeemed at the machine for cash regardless of what (if anything) is listed in

the payee field. Again, the payee section of the check can include a name, include "cash", or remain empty. That is, in an exemplary embodiment the payee field is not a factor that the computer system **196** uses in determining whether the check can be exchanged for cash. However, the code that is correlated with the check is a factor. One must provide to an automated banking machine both the check and the code in order to receive the cash.

[0279] Furthermore, the code allows the check to be anonymously cashed at the automated banking machine. That is, the code can be presented at the machine to exchange the check for cash without the check presenter (machine user) having to provide any user inputs to the machine which personally identify the person presenting the check. Nor does the check bearer (machine user) need to provide a card or other identifying feature which is normally necessary in order to operate the machine for other transactions. Again, in the exemplary embodiment only the check and the code needed to be provided the machine. Upon determined correspondence of appropriate inputted and stored check data, the machine can dispense the check amount in the form of cash to the (anonymous) machine user. Of course these approaches are exemplary and other approaches can also be used.

[0280] If a completed coded check that is made out to "cash" becomes lost or stolen it cannot be anonymously cashed. Again, the code is needed to anonymously cash the check. As a result, any attempt to fraudulently cash the check (away from an automated banking machine) should result in personal identification being required to be shown.

[0281] In the exemplary embodiment, the computer **204** operates at (or near) the time of outputting (to the check maker) the certification data, to cause funds corresponding to the check amount to be placed on hold (or reserved) for purposes of later paying (cashing) the check. In this way, a check recipient is assured that the amount of the check will be paid regardless of additional checks which may be drawn on the checking account after the check is written. In some exemplary embodiments, the computer **204** operates to transfer funds from the check maker's account to a special (reserve) account, such as an accrued value account, for the specific purpose of guaranteeing payment of the check. In other embodiments the computer **204** may operate to reserve the amount of the check without making an immediate deduction from the maker's account. The computer **204** can reserve (in a system account) the check amount on behalf of the check maker in exchange for charging the check maker's credit card account for the check amount plus a cash lending/holding fee. The system account can be out of the control of (not accessible to) the check maker. Of course these approaches are exemplary, and in other embodiments other approaches may be used.

[0282] In an example transaction, the check maker (before signing the check) provides its correlated certification data to a potential check recipient. The recipient is able to verify that the check will be paid when it is later presented by the recipient. This may be accomplished by the recipient contacting the institution or other entity upon which the check is drawn. The recipient may do this by communicating with the computer system **196** through the consumer interface device **208**. This might be done, for example, via a wireless communication device before the potential recipient of the check actually accepts the check as payment from the check maker.

[0283] In an exemplary embodiment, the potential check recipient can use a cell/smart phone to communicate with the consumer interface device **208**. The recipient provides inputs which correspond to the certification data. Other inputs may also be necessary to further identify the particular check. The inputs may be provided in response to programmed prompts or other outputs sent from the interface device. In response to the received inputs, as well as other data that the system may request from the potential check recipient, the computer **204** can operate to determine if the check is certified (e.g., will be honored). The computer makes this determination responsive to comparison of data stored in the data store **206** regarding the check. If the computer determines that the check is not certified (e.g., will not be honored), then the potential check recipient is so informed through the consumer interface. However, if the computer **204** determines that the check is guaranteed to be payed (e.g., redeemable for cash), then the consumer interface device **208** outputs to the potential check recipient, assurance that the check will be honored for a particular amount. The assurance output that is provided can include detailed information that uniquely identifies the check and its check amount. Based on the information received, the potential recipient can decide whether to accept the check as payment.

[0284] This exemplary approach provides convenience in transaction situations that are conducted away from electronic devices that are normally used to conduct transactions. As can appreciated, the system allows a certified personal check to be used in place of cash. Yet the check can be without any visible evidence that it has been certified. For example, a person wishing to purchase an item at a local flea market may write a check that the recipient can quickly verify will be honored via a wireless phone or other remote communication device. Likewise, persons passing through a particular area that are selling crafts or food, doing odd jobs, or other activities not associated with a fixed place of business, may accept checks with assurance that the checks will be honored. As previously discussed, a check recipient may receive a check made out to "cash" which can be cashed in a (secretive) manner which is not traceable back to the check recipient. Of course these examples are exemplary.

[0285] In an exemplary embodiment, the check for cash approach described herein provides dual benefits. The paying party has the benefit of paying by check, whereas the receiving party has the benefit of essentially receiving payment in cash.

[0286] As previously discussed, a recipient of a "cash" check correlated with certification code can exchange it for cash at an automated banking machine. The exemplary machines are programmed to operate so as to enable the machine to receive the check without requiring the user to first input a debit or credit card (or other machine actuating device). That is, the recipient can anonymously redeem the check for cash at any system machine without being required to provide any machine user identification data (e.g., a user card) to the machine.

[0287] Also, a coded check itself is still valid without the recipient using the certification code. That is, the recipient of a coded check can still use the check in a normal machine transaction which requires the machine user to provide identification. For example, the recipient may provide identification (via a user card) to an automated banking machine in order to have the check be accepted by the machine in the course of depositing the check into the recipient's bank account. Likewise, the check may be exchanged (redeemed) for cash (or other value) in other transaction environments,

such as by a bank teller, by a check service provider, or in a retail establishment. That is, a received coded check can be used in a conventional check transaction that does not require use of the code. However, the code provides the recipient the added benefit of being able to remain anonymous (without being required to provide recipient identification) while exchanging the check for cash at an automated banking machine. Also, because normal (and longer) machine usage is not needed, the code allows the recipient to quickly receive cash.

[0288] An exemplary redeeming operation will now be described. The process enables a check recipient to cash a coded check without being personally identified. The recipient provides inputs through at least one input device of an automated banking machine to indicate that they wish to cash a check of the type that has associated certification data. This may be done by providing user inputs to the machine to select a transaction description output on a machine display or through other methods of providing inputs so as to indicate to the machine the type of transaction that the machine user (the check recipient) wishes to conduct.

[0289] In an exemplary embodiment, an appropriate transaction option button is displayed on an automated banking machine's touch screen. The button (box) is associated with a user selecting to cash a certified check. For example, the box may indicate "cash a certified check". Touching the box provides at least one more display screen which instructs the user (on how) to insert the check and the code. For example, responsive to operation of at least one processor associated with the machine, the machine operates to instruct the user to input (insert) the check into the machine and to provide the certification data through at least one input device of the machine (e.g., a machine keypad or touchscreen).

[0290] In an exemplary embodiment, the machine is operative through operation of a check imaging device (of its check reader) to produce or generate image data (e.g., an electronic image) corresponding to a visual image of at least one side the check. At least one computer (e.g., machine computer or controller) associated with the machine then operates to determine from the generated image data, identifying data associated with the check. This may include, for example, determining data included in the check micr line, data included in a check number, or other data from the check. The computer associated with the machine is also operative to resolve at least one amount value based on the generated image data. This check amount value may include the courtesy amount, the legal amount, or both. Magnetic check data may also be read by the machine for use in determining the validity of the check for check cash purposes.

[0291] In an exemplary embodiment, the computer associated with the machine is configured to operate software, programming, and/or applications, etc. capable of identifying characters in generated check image data in order to resolve check data such as the micr line data, check number data, check amount data (e.g., courtesy amount and/or legal amount), name data (e.g., payee and/or payor), endorsement data, and/or other data from the check image. The computer associated with the machine (e.g., machine computer) can also deskew the check image data and place it in registration with an imposed coordinate system. The check image data can also be manipulated in other ways in order to attempt to translate the image so as to find appropriate data. This manipulation can include shifting, rotating, transposing, and flipping check image data. The computer associated with the machine can also apply template logic to the manipulated check image. Examples of systems and methods related to obtaining data from a check image may be found in U.S. Pat. No. 8,141,774, which is herein incorporated by reference.

[0292] The exemplary automated banking machine is operative to thereafter communicate with the computer system **196**, which may include a server. The server can be part of a transaction host, a check verification service, a system server, etc. In the exemplary embodiment, the machine is operative to communicate to the computer system, obtained data corresponding to the check identifying data, the certification data inputted by the user, and the amount data (obtained from the check data and/or inputted by the user). Of course some embodiments may not transmit all of these data items, and other embodiments may transmit additional data items.

[0293] In still other embodiments the computer system **196** may be operative to transmit data corresponding to the stored check identifying data and/or the stored certification data to the automated banking machine so that the machine itself can validate the data against what it has received and/or resolved from the data inputted by the machine user. It should be understood that in an exemplary embodiment the data communicated between the machine and the at least one computer is subject to security procedures such as encryption, transmission through a virtual private network, or other methodologies to maintain the secrecy thereof.

[0294] In the exemplary embodiment, the computer **204** (which is remote from the automated banking machine) is operative to determine whether the received check data and certification data correspond to data stored in the data store **206**. The computer **204** is also operative to determine if the check amount determined by the machine corresponds to (matches) the check amount that is stored in the data store **206**.

[0295] In the exemplary embodiment, if the certification data, check identifying data, and/or amount data provided at the automated banking machine do not correspond to the data stored in the data store **206**, then at least one communication to the machine indicating that the transaction is not authorized is provided by the computer **204**. The machine is operative responsive to such a transaction disapproval communication to advise the user through at least one output device (e.g., a display) that the check cashing transaction request has been denied. In an exemplary embodiment, the check is returned to the user in circumstances where it does not appear that a fraud is being committed. Of course in some embodiments, if it appears that the user is attempting to perpetrate a fraud, for example if the check is a duplicate of one that has already been redeemed for cash, then the machine may operate in accordance with its programming to capture and store the check in the machine. Of course this approach is exemplary.

[0296] If the computer **204** determines that the certification data, check identifying data, and/or amount data sent from the machine corresponds to data (in data store **206**) for a valid check, then the computer communicates to the machine transaction authorization data indicating that the check can be redeemed for cash. The machine **198**, **200** operates in response to such transaction approval communication to operate at least one cash dispenser in the machine to dispense to the user, cash (e.g., paper currency) corresponding to the check amount. That is, as a result of receiving the coded check and the correct code, the machine causes cash corresponding

to the check amount to be dispensed. No machine user identification is included in the (journal) record of the check cashing transaction.

[0297] In an exemplary embodiment the machine further operates to store the check in the machine. Alternatively, the machine may destroy the check, which was previously imaged. The check image (or copy thereof) can be sent to a check reconciliation center for later usage.

[0298] As discussed herein in an exemplary embodiment, the recipient of a coded check is able to receive cash in exchange for the check without having to provide to any user input devices of the automated banking machine, data which personally identifies the particular person receiving cash for the check. Thus, for example, the user (check recipient) does not have to input a card, biometric input, or other personal identifying data as a condition to receive cash in exchange for the check. The check recipient does not have to provide any identifying data in order (as a requirement) to cash the check. Neither the machine nor a financial institution need to know the identity of the recipient in order to allow (authorize) the check cashing transaction. Thus, the recipient can remain anonymous throughout the entire check cashing process.

[0299] Another exemplary process of a recipient anonymously exchanging a check for cash will be described. The recipient (or someone acting on behalf of the recipient) inserts a previously coded (paper) check into an automated banking machine. The machine reads the check data, which may be read from a check image. As previously discussed, the read check data can include check maker data, account data, check number data, and/or check amount data, etc. The machine sends the read check data to a host (server). The host has access to a data store which includes the data on checks that were pre-certified to be good as cash (and anonymously cashed). The stored pre-certified check data can include check maker data, account data, check number data, the check amount data, the code, etc. The host can determine by use of the data store whether a predetermined level (e.g., the check amount) of the check data (received from the machine) corresponds to (matches) stored check data of a pre-certified check. The host can inform the machine of a positive determination (i.e., that read check data matched check data for a particular pre-certified check). The positive determination causes the machine to ask the recipient to enter the unique code assigned to the inserted check. The machine sends the entered code to the host. The host can determine by use of the data store whether the entered code (received from the machine) corresponds to (matches) the stored code of the particular pre-certified check. Upon matching of the (entered and stored) codes, the host informs the machine that the check can be cashed. The machine then operates to dispense to the user, an amount of cash that corresponds to the check amount. The host can modify the data store to reflect that the pre-certified check was cashed. In other embodiments, the machine can operate to send to the host in at least one message that requests authorization of the check cashing transaction, both the read check data and the inputted code. That is, the check data and the code data do not have to be sent separately (and at different times) to the host.

[0300] The host server may be the automated banking machine's financial transaction host. The host can also be different (separate) from the financial transaction host, such as a third party server. Thus, the machine may communicate with the host server independent of its communication with the financial transaction host. The machine (or the host server) can notify the financial transaction host of the check cashing transaction.

[0301] As can be appreciated, the described exemplary process of anonymously cashing a check only requires the recipient to provide a few inputs to an automated banking machine. In an exemplary embodiment the inputs include: at least one input which notifies the machine as to the type of transaction being requested (i.e., an anonymously check cashing transaction); input (insertion) of the check into the machine; and input of the check code to the machine. In a further exemplary embodiment, the machine can sense that a check is near a check input slot, where upon the check is automatically received by the machine. Thus, in the further exemplary embodiment, only check insertion and code input are needed to be provided by the recipient in order to receive cash for a coded check.

[0302] Providing the code alone to an automated banking machine will not result in a dispense of cash that corresponds to the check amount. Rather, both the check (or its check data, which may be in an electronic format) and the code need to be provided to the machine during the same user session. This dual providing arrangement protects against the check being fraudulently cashed if the code is inadvertently made publically known (or stolen).

[0303] The check data that needs to be provided to the automated banking machine can be in different data formats. For example, the check data may be in the form of a physical (tangible) paper check. However, the check data may also be in the form of an electronic check, a check image, or a virtual check. The machine is likewise configured to be able to receive the check data in the different data formats. For example, an exemplary automated banking machine is operative to receive check data that is wirelessly provided from a mobile device of the recipient. The check data can be stored in the mobile device until the coded check is cashed. The mobile device can comprise a cell phone, a smart card, and/or an electronic wallet, etc. Also, the electronic wallet and/or stored value can be stored in memory of the mobile device (e.g., smart phone). The mobile device can initially receive the check data in an electronic format from the maker of the check. Alternatively, a tangible paper check may be converted to another format (e.g., an electronic check image) to enable storage of its check data in the mobile communication device.

[0304] As previously discussed, a potential recipient of a particular check can communicate with a service provider system computer (e.g., at least one host contact computer or server) to verify whether the particular check will be paid by the entity upon which the check is drawn. The communication can be carried out through use of a mobile communication device (e.g., a mobile phone) of the potential recipient. The potential recipient provides both check identification data and check certification code data to the service provider system. Based on the data provided, the service provider system sends an informative message to the potential recipient with regard to whether the check will be honored for a check amount (as a valid pre-certified check). As previously discussed, the message can be provided in various data formats, including voice, text, e-mail, web pages, etc.

[0305] In an exemplary embodiment, when the service provider system **196** operates on behalf of a potential recipient to determine that a (pre-certified) check is valid, then the verification message provided to the potential recipient can include additional information. This information may include

advertisements, or knowledge assisting in cashing of the check. For example, the information may indicate the location of (e.g., an address of or directions to) at least one automated banking machine that is configured to cash checks anonymously. This information may also include step by step instructions on how a pre-certified check can be cashed at the indicated at least one machine.

[0306] In the exemplary embodiment, the service provider system **196** can determine the location of the nearest automated banking machine (relative to the potential recipient) that will allow the potential recipient to anonymously cash the pre-certified check. The message information (which is sent to the potential recipient) includes this machine location data. The provided location data can include (provide) the shortest route (directions) from the potential recipient's current location to the determined nearest machine. The closeness of the indicated machine may be a factor that induces the potential recipient to accept the check from the check maker.

[0307] The current location of the potential recipient can be provided to the computer system **196**, such as when the recipient initially contacts the consumer interface **208**. The recipient's location data may be communicated from the recipient's mobile device (e.g., a mobile phone) to the consumer interface. For example, the recipient's mobile device (e.g., a smart phone, browser, etc.) can have GPS location data. The computer system **196** is configured to automatically receive this GPS data (from the mobile device) during communication with the mobile device. Alternatively, the potential recipient may be requested to provide (by manual or voice input) his/her location (address) data to the computer system in order to be apprised of the nearest automated banking machine (and map directions and travel time thereto).

[0308] The location of the closest/nearest automated banking machine that is configured to carry out the recipient's desired transaction (anonymous cashing of a check) can also be provided by the computer system **196** (or a computer thereof) to the recipient's mobile device in the form of GPS location data. The mobile device can have access to a location directing application (e.g., navigation application software) that produces directions for traveling from the mobile device's current GPS location to the machine's GPS location. The mobile device may also be part of (or can be linked with) an automobile's navigation system which can function to produce the road driving directions. The navigation system being used can be updated in realtime with regard to travel delays, accidents, detours, etc. to provide directions based on the fastest travel time to the nearest machine which allows the check to be (anonymous) cashed.

[0309] Again, a check that can be used in the exemplary embodiments is not limited to a paper check but can also comprise a check that is in an electronic format. That is, a payor may provide an electronic check to a check recipient. Thus, the configured automated banking machine can also allow the recipient to receive (tangible) cash in exchange for a monetary value (e.g., an electronic check, virtual cash, etc.) stored in memory of their mobile device (e.g., an electronic/digital wallet, smart phone, tablet, i-Pad, etc.).

[0310] In some embodiments, fees may be imposed on the check maker and/or the check recipient for the service provided by the computer system and/or machine. The computer system may deduct a check maker fee at the time the certification data is issued and/or a deduction may be made from the amount dispensed to the automated banking machine user. For example, the dispensed cash that corresponds to the check amount may include a transaction fee, which results in the actual amount of cash dispensed being less than the full amount indicated on the check.

[0311] As previously discussed, stored value in the form of electronic check data can be provided to a cash dispensing automated banking machine in exchange for cash. The stored value can be wirelessly transferred from the person's mobile device to the machine. However, in other exemplary embodiments, other types (or forms) of stored value besides check data can be provided to an automated banking machine in exchange for cash. For example, a recipient's mobile device (e.g., phone, smart card, stored value card, electronic wallet, etc.) may receive cash value (e.g., electronic or digital cash) from another person, such as a payor making a payment during a transaction. The stored (cash) value in the phone can then be used as good as cash. Examples of systems and methods related to the storage and use of stored value may be found in U.S. Pat. No. 6,315,195, which is herein incorporated by reference. Examples of wireless communication between an automated banking machine and a mobile phone can be found in U.S. Pat. No. 7,992,776, which is herein incorporated by reference.

[0312] The adding of the cash value to the recipient's mobile device may be by the recipient (manually) inputting a given code. The recipient's phone may also read the code, such as from a barcode. Alternatively, the cash value may be wirelessly added or transferred to the recipient's phone from the payor's mobile device (e.g., a phone). Near field communication (NFC) signals or radio frequency identification (RFID) signals are some of the data communication modes that can be used by the recipient's phone to receive the cash value from the payor's mobile/portable device. Also, the cash value may be received by the recipient's mobile device from a different device or a stationary (self-service) machine, such as an automated banking machine, a vending machine, a fuel pump device, a check out register, a smart card, a stored value card, electronic wallet, Internet, Bluetooth, etc.

[0313] The cash value data can be stored in the mobile device until it is used. Use of the cash value can include all or part of it being converted to cash, being used in a transaction (e.g., a purchase, a deposit), or being transferred to another device (e.g., a smart card), etc.

[0314] In an exemplary embodiment, a recipient's phone gets data from someone (or something) during a transaction, where the data is associated with a monetary value (worth). The data can actually be the monetary value (e.g., such as digital cash) or can be used to provide access to the actual monetary value. The cash value data can be stored (as stored value) in memory of the phone. The stored value can be used like cash to purchase goods or services. In the exemplary embodiment, the recipient can use their phone to turn this stored value into cash at a cash dispensing automated banking machine. The cash dispense can be based solely on the machine receiving stored value from the phone.

[0315] The stored value data in the phone may be encrypted or stored using schemes to prevent fraud or tampering therewith. Near field communication (NFC) signals, radio frequency identification (RFID) signals, hand shaking encryption techniques, or other wireless communication formats are some ways that can be used by the recipient (phone bearer) to provide stored value from their phone to an automated banking machine in exchange for cash. Cash can be received in exchange for either the entire cash value or a portion thereof. The phone's memory is accordingly modified to reflect the

cash value amount that was spent or used (by being transferred from the phone to the machine).

[0316] An alternative exemplary embodiment will now be discussed. During a transaction the recipient's phone can receive (from a payor) data that includes both code data and value data (e.g., data indicative of a cash value). The automated banking machine needs to receive both the value data and the code data in order to dispense an amount of cash that corresponds to the cash value. Thus, the cash dispense is dependent (based) on the machine receiving the correct code. As previously discussed, the computer system **196** can be used by the payor, prior to giving the code to the recipient, to cause the code to be correlated (in a data store) with a cash value.

[0317] In a first alternative embodiment there is no actual cash amount stored in the phone. Rather, the value data stored in the phone only points to or indicates an amount of cash value. The automated banking machine can receive input of the code data and the value data from the user's phone. The machine sends both the received code data and the value data (which indicates a value) to the machine's host. For example, the value data may point to (reflect) a value of $100. The host can determine if the received code data is linked with any cash value in the data store of the computer system **196**. The host can also verify whether this determined cash value ($100) corresponds to the value ($100) indicated by the received value data. Upon verification that the found cash value ($100) corresponds to the indicated value ($100), the host can then authorize the machine to dispense a cash amount which corresponds to the verified cash value ($100). Of course the ordered steps of verification may differ with regard to host use of the received value data and code data. That is, one data (code data or value data) can be used to verify the other data. The data store can be accordingly updated to reflect use of the code.

[0318] As can be seen, the first alternative embodiment allows a recipient to receive payment in the form of data (code data and value data) instead of cash. In a manner previously discussed, a payor can have the computer system **196** reserve a cash amount for a code. This enables a potential recipient of a payment (via code data and value data) to first contact the computer system **196** to verify whether the code data and the value data are guaranteed for a specified amount of cash redeemable at an automated banking machine. As can be appreciated, the recipient can use received code data and value data to anonymously obtain cash at an automated banking machine. In a manner previously discussed, during communication between the potential recipient and the service provider system **196**, the potential recipient can be informed of the location of the nearest automated banking machine (relative to the potential recipient) that will allow the potential recipient to anonymously obtain the cash.

[0319] In a second alternative embodiment there is an actual cash amount (stored value) stored in the phone. That is, the value data stored in the phone has an actual monetary value and can be used like cash. This embodiment is similar to some previously discussed embodiments where a phone stores both coded check data and its code. In order to exchange the phone's stored value (electronic cash) for (paper) cash from an automated banking machine, the phone user has to give the machine either the code or personal identification. Providing the code allows the transaction to be anonymous.

[0320] In the second alternative embodiment, the automated banking machine receives the code data and amount data from the machine user. The amount data indicates the (numeric) value ($60) of the cash value that is stored in the phone. The code data and/or amount data may be read/received by the machine directly from the phone, or manually provided by the machine user. The machine sends both the code data and the amount data to the machine's host. The machine's host verifies whether the received code data is linked in the data store (of the service provider system **196**) with the value ($60) indicated by the received amount data. Upon verification, the machine is authorized to dispense a (paper) cash amount up to the (numeric) value ($60) in exchange for receiving a similar (electronic) cash amount from the phone's stored value. For example, after the machine receives $60 in electronic (digital) cash from phone memory, then the machine dispenses $60 in paper cash to the machine user. The process allows the phone holder/machine user to anonymously receive cash from the automated banking machine in exchange for electronically stored value. The phone holder/machine user does not need to provide any personal identification as a condition for receiving the paper cash. The data store of the service provider system **196** can be accordingly updated to reflect use of the code.

[0321] As previously discussed, the computer system **196** can be used by both the payor to reserve a cash amount and the potential recipient (of a payment from the payor) to verify that the cash amount is reserved. During communication between the potential recipient and the service provider system **196**, the potential recipient can be provided with the location of the nearest automated banking machine (relative to the potential recipient) that allows the cash to be anonymously obtained.

[0322] In a third alternative embodiment no actual cash amount is stored in the (recipient's) phone. That is, only code data is stored in the phone. The code data is linked to an account for a specific amount. As previously discussed, the account may be a reserve account held by the service provider system **196** or an active account held by the payor. The code data can comprise (an encrypted combination of) both a unique (or payor selected) code and the encrypted account number of the account. The machine can wirelessly receive the code data from the user's phone. The machine sends the code data to a host. The host determines (via a data store) whether the code data is valid. If valid then the machine is authorized to dispense a cash amount which corresponds to the specific amount. The data store is modified to reflect that the account was reduced the specific amount. As can be seen, no personal identification data is required to be input to the machine by the user in order to receive dispensed cash. That is, the machine is configured to allow the exchange of code data for cash to be carried out anonymously by a machine user.

[0323] In one example, the arrangement allows the payor to safely provide the unique code (i.e., only a portion of the total code data) to the potential recipient of a payment from the payor. This is because the unique code alone is not usable to obtain cash (e.g., currency notes) from an automated banking machine. Rather, the full code data is required by the machine in order to dispense the corresponding cash. The potential recipient can communicate with the computer system **196** to receive both verification that the unique code corresponds to a particular amount of reserved cash and information on the nearest automated banking machine that can anonymously cash the code data. Upon the recipient agreeing to accept the

electronic payment, the payor provides the entire (full) code data to the recipient's phone. In some embodiments, transfer of the (encrypted) code data to the recipient's phone causes the code data to be removed/erased from the payor's phone. At this point, the arrangement allows the recipient to again contact the computer system **196** to verify that the entire code data is valid. Additionally, as another security feature, the machine may be configured to only accept code data from a phone, and not by manual input.

[0324] In still other exemplary embodiments, an automated banking machine can communicate with the service provider system **196** (or another host) independent of its communication with its financial transaction host. For example, the machine may carry out communication with a security code host, where the communication does not involve the financial transaction host. The security code host may be used by the machine to receive initial verification that a code is valid before the machine requests transaction authorization for the cash dispense from the transaction host. The machine may send the received verification data to the transaction host in the transaction authorization request.

[0325] As previously discussed, an automated banking machine can anonymously cash a check by dispensing tangible currency. In a further exemplary embodiment, the machine can anonymously cash a check by dispensing a cash value to a phone. The machine can dispense (to the phone) the total check amount as an electronic stored value. The machine can also dispense part of the total check amount as tangible currency and the other part as stored value. The stored value in the phone (like in a smart card) can then be used like cash in future transactions (e.g., purchases, etc.). Thus, an exemplary automated banking machine is configured (via associated programming, software, firmware, circuitry, etc.) to anonymously cash a check by dispensing tangible cash, digital cash (stored value), or a combination thereof. In yet further embodiments, instead of providing physical cash or digital cash, the exemplary machine can also provide (either physically or electronically) other forms of value, such as coupons, tickets, pictures, stamps, phone cards, gift cards, fuel cards, music, videos, movies, Internet usage time, services, etc.

[0326] Also, it should be understood that an exemplary automated banking machine can be configured to anonymously provide tangible cash in exchange for any feature of value that is received from a mobile device (e.g., phone). That is, the feature of value that can be accepted by the machine does not necessarily need to be stored value, an electronic check, digital cash, etc. Rather, the feature of value stored in the phone can be other data that is merely linked to a monetary amount. For example, a feature of value can comprise a (alphanumeric or audible) code, password, voice message, (payor's) telephone number or ID, etc.

[0327] Again, an exemplary arrangement allows a recipient to receive (as a payment, gift, etc.) a feature of value from someone (or some device/machine). The feature of value may be provided to the recipient in several different formats, including verbal, printed, electronic, and/or magnetic form. For example, the feature of value may be wirelessly received into a personal device (e.g., a mobile phone, electronic wallet, etc.) of the recipient. The recipient can then present the feature of value to an automated banking machine in order to receive dispensed cash. As previously discussed, the recipient may need to present other (additional) data along with the feature of value to the machine in order to receive the cash from the machine.

[0328] It should be understood that cameras **226** may be present for security purposes to capture images of automated banking machine users conducting transactions. However, for purposes of this disclosure these security images are not considered to be required identification input by a user in order for the user to (anonymously) receive cash for provided data (e.g., a particular coded check, code data, etc.). Typically, in the absence of fraud or other circumstances, the captured image data of machine users is only stored on a temporary basis and then periodically discarded. In this way, capturing a security image of a person is not a requirement for a machine to allow the person to anonymously receive cash for a check, stored value, etc.

[0329] Of course these approaches are exemplary, and the principles described may be used in conjunction with other types of systems and devices. Thus, the features and characteristics of the exemplary embodiments described herein achieve desirable results, eliminate difficulties encountered in the use of prior devices and systems, solve problems, and attain one or more of the objectives stated above.

[0330] In the foregoing description certain terms have been used for brevity, clarity and understanding, however no unnecessary limitations are to be implied therefrom because such terms are for descriptive purposes and are intended to be broadly construed. Moreover, the descriptions and illustrations given herein are by way of examples, and the invention is not limited to the exact details shown and described.

[0331] In the following claims, any feature described as a means for performing a function shall be construed as encompassing any means capable of performing the recited function, and shall not be deemed limited to the particular means shown in the foregoing description or mere equivalents thereof.

[0332] The term "non-transitory" with regard to computer readable medium is intended to exclude only the subject matter of a transitory signal per se, where the medium itself is transitory. The term "non-transitory" is not intended to exclude any other form of computer readable media, including media comprising data that is only temporarily stored or stored in a transitory fashion. Should the law change to allow computer readable medium itself to be transitory, then this exclusion is no longer valid or binding.

[0333] Having described the features, discoveries and principals of the invention, the manner in which it is constructed, operated, and utilized, and the advantages and useful results attained; the new and useful structures, devices, elements, arrangements, parts, combinations, systems, equipment, operations, methods, processes, and relationships are set forth in the appended claims.

We claim:

1. A method comprising:

(a) operating a computer system affiliated with a financial entity, to receive a code sent from a mobile phone,

wherein the computer system is associated with at least one data store,

wherein the at least one data store is configured to respectively associate check cashing codes with financial checks,

wherein each respective check is associated with a respective check amount,

wherein each respective check can be anonymously cashed by a person at least one cash dispensing automated banking machine which includes a check imager and a currency dispenser, without

the person being required to input any machine user identification data as a condition for cashing the respective check,

wherein the at least one data store is configured to respectively associate machine location data with each of the at least one cash dispensing automated banking machine;

(b) operating the computer system to determine through use of the at least one data store, that the code received in (a) corresponds to a check cashing code;

(c) operating the computer system to determine through use of the at least one data store, which of the at least one cash dispensing automated banking machine is nearest to the mobile phone; and

(d) operating the computer system to send to the mobile phone, at least one message that includes

(i) responsive at least in part to (b), verification that the code received in (a) corresponds to a check that can be anonymously cashed;

(ii) an amount associated with the check in (i); and

(iii) responsive at least in part to (c), machine location data associated with the nearest machine.

2. The method according to claim **1** wherein (a) includes receiving the code in a request for directions to an automated banking machine which includes each of:

at least one reader,

a check imager,

a currency dispenser operative to dispense currency from the machine,

at least one machine computer,

wherein the at least one machine computer is operative to cause user data read by the at least one reader to be compared with user information stored in at least one data store,

wherein the at least one machine computer is operative to authorize the user to use the machine carry out the check cashing transaction responsive to

computer-determined correspondence between user data read by the at least one reader and stored user information, and

wherein the at least one machine computer is operative to cause a funds transfer involving a financial account which corresponds to user data read by the at least one reader.

3. The method according to claim **2** wherein (a) includes receiving the request for directions to an automated banking machine which is part of a banking system,

wherein the at least one reader includes both a card reader and a biometric reader,

wherein the at least one machine computer is operative during the check cashing transaction to

cause card data to be read through operation of the card reader, and

cause biometric data to be read through operation of the biometric reader, and

cause authorization of the user to carry out the check cashing transaction, responsive at least in part to both

computer-determined correspondence between card data read by the card reader and stored card information, and

computer-determined correspondence between biometric data read by the biometric reader and stored biometric information,

wherein the at least one machine computer is operative during the check cashing transaction to apply different check format templates to an electronic image of a financial check to read check data therefrom,

wherein each of the templates corresponds to at least one area of a check where at least one visible character is located,

where the at least one visible character includes micr characters.

4. A method comprising:

(a) operating a computer system associated with at least one data store, to receive at least one message including a code sent from a mobile communication device;

(b) operating the computer system to determine that the code received in (a) is associated with financial check data in the at least one data store; and

(c) subsequent to (b), operating the computer system to send to the mobile communication device, at least one message that includes

(i) verification data usable by the mobile communication device to provide to a user of the mobile communication device, information indicating that the code corresponds to a check that can be cashed at least one automated banking machine without requiring any input of machine user identification data as a condition for cashing the check, and

(ii) location data usable by the mobile communication device to provide to the user of the mobile communication device, information associated with location of a particular machine of the at least one automated banking machine that is nearest to the mobile communication device.

5. The method according to claim **4** wherein the mobile communication device comprises a mobile phone that includes a display,

wherein in (c) both the verification data and the location data are displayable by the display.

6. The method according to claim **4** wherein in (c) the location data includes the information, wherein the information includes a geographical address of the particular machine.

7. The method according to claim **4** wherein in (c) the location data includes the information, wherein the information includes a GPS location of the particular machine.

8. The method according to claim **4** wherein in (c) the information in (ii) comprises directions from the mobile communication device to the particular machine.

9. The method according to claim **8** and further comprising

(d) prior to (c), operating the computer system to produce the directions;

wherein in (c) the location data includes the directions produced in (d).

10. The method according to claim **9** wherein the at least one message received in (a) includes device location data associated with location of the mobile communication device, and wherein (d) includes using the device location data to produce the directions.

11. The method according to claim **10** wherein the device location data received in (a) corresponds to a GPS location of the mobile communication device, and further comprising

(e) prior to (d), operating the computer system to determine that the particular machine is nearest to the mobile communication device based at least in part on the GPS location received in (a).

12. The method according to claim **4** wherein in (c) the verification data comprises information that confirms that the code corresponds to a pre-certified check that is backed by funds previously reserved for a particular check amount.

13. The method according to claim **12** wherein in (c) the verification data comprises information that confirms that the code is valid for an electronic check having the particular check amount.

14. The method according to claim **13** wherein in (c) the information in (ii) is associated with location of the nearest machine that can exchange the electronic check for cash without requiring any input of machine user identification data as a condition for exchanging the electronic check.

15. A method comprising:

(a) operating at least one computer associated with a service provider system to receive communication data sent through a personal communication device,

wherein the communication data includes location data associated with a current location of the personal communication device;

(b) operating the at least one computer to determine relative to the current location of the personal communication device, the nearest automated banking machine configured to cash a check without requiring any input of machine user identification data as a condition for cashing the check; and

(c) operating the at least one computer to cause machine location data corresponding to location of the nearest automated banking machine determined in (b), to be sent to the personal communication device.

16. The method according to claim **15** wherein in (c) the machine location data includes directions from the current location of the personal communication device to the location of the nearest automated banking machine.

17. The method according to claim **16** and further comprising

(d) prior to (c), operating the at least one computer to produce the directions.

18. The method according to claim **15**

wherein the at least one computer is associated with at least one data store,

wherein the at least one data store includes check cashing codes for each of a plurality of financial checks,

wherein the at least one data store includes machine location information for each of a plurality of automated banking machines,

wherein in (a) the communication data includes a code, and further comprising

(d) operating the at least one computer to determine that the code received in (a) corresponds to a check cashing code in the at least one data store;

wherein (c) includes operating the at least one computer to cause to be sent to the personal communication device, verification data indicating that the code corresponds to a check that can be cashed at least one automated banking machine without requiring any input of machine user identification data as a condition for cashing the check.

19. The method according to claim **18** wherein the personal communication device comprises a mobile phone,

wherein in (c) both the machine location data and the verification data are sent to the mobile phone.

20. The method according to claim **15** wherein in (a) the location data includes a GPS location data corresponding to the current location of the personal communication device.

* * * * *